



ASTOTIN CREEK

RESILIENCY STUDY

Resiliency Action Plan

April 2022



Territorial Acknowledgment

Strathcona County honours the past, present and future First Peoples of this land. We acknowledge that this land has embraced and nourished the Cree, Métis, Blackfoot, amongst many others, for generations. We recognize Strathcona County is within Treaty Six Territory and the homeland of the Métis Nation of Alberta, Region Two and Four.

Strathcona County has an inherent responsibility to foster healthier relationships with Indigenous Partners. We will strive to respond to the Calls to Action as outlined by the Truth and Reconciliation Commission.

Strathcona County is close in proximity to Enoch Cree Nation (maskêkosihk), Ermineskin Cree Nation (neyaskweyahk), Louis Bull Tribe (kisipatinahk), Michel First Nation, Montana First Nation (akamihk), Papaschase First Nation, Samson Cree Nation (nipisikopahk), and Saddle Lake Cree Nation (onihcikiskwapiwinihk).

Furthermore, the geographic boundaries of Strathcona County includes parts of Regions Two and Four of the Métis Nation of Alberta, and are near the Elizabeth Métis Settlement, Fishing Lake Métis Settlement, Buffalo Lake Métis Settlement, and Kikino Métis Settlement.

*We recognize the importance of allying with First Peoples and taking steps to foster a healthier relationship. As such, we will demonstrate **manacitôwin**, the Cree word meaning respect for each other.*



Signatures & Authorizations

PROJECT MANAGEMENT



Mikaela Hanley, M.Eng., P.Eng.
Project Manager (April 2021- April 8, 2022)

PROJECT MANAGEMENT



Joshua Maxwell, M.Sc., P.Eng., PMP
Project Manager (April 8, 2022- Project end)

RESISTANCE PLANNING:



Kaitlynn Livingstone, M.A.Sc., P.Eng
Resilience Planning Lead

COMMUNITY ENGAGEMENT:




Shawn Bravender, CP3, RPP, MCIP, CET
Community Engagement Lead

ECOLOGICAL PLANNING:



Dee Patriquin, Ph.D, P.Biol, RPBio
Ecological Assessment Lead (April 2021 -
Feb 2022)

INDIGENOUS ENGAGEMENT:



Amanda Doyle, M.Sc
Indigenous Engagement Lead

STORMWATER MANAGEMENT PLANNING:



Juan Upegui, M.Eng., P.Eng.
Stormwater Management Lead

HYDROTECHNICAL ANALYSIS:

Prepared by

HYDROTECHNICAL ANALYSIS:

Reviewed by

Ana Hosseinpour, Ph.D, P.Eng.
Water Resource Engineer

Vincent Cormier, M.Sc., P.Eng.
Hydrotechnical Engineering Lead

Permit to practice

Disclaimer

WSP prepared this report solely for the use of the intended recipient, Strathcona County, in accordance with the professional services agreement. The intended recipient is solely responsible for the disclosure of any information contained in this report. The content and opinions contained in the present report are based on the observations and/or information available to WSP at the time of preparation. If a third party makes use of, relies on, or makes decisions in accordance with this report, said third party is solely responsible for such use, reliance or decisions. WSP does not accept responsibility for damages, if any, suffered by any third party as a result of decisions made or actions taken by said third party based on this report. This limitations statement is considered an integral part of this report.

The original of this digital file will be conserved by WSP for a period of not less than 10 years. As the digital file transmitted to the intended recipient is no longer under the control of WSP, its integrity cannot be assured. As such, WSP does not guarantee any modifications made to this digital file subsequent to its transmission to the intended recipient.



Table of Contents

Introduction 7

1.1	Importance of Resilience for Astotin Creek	11
1.2	Project Approach and Objectives	13

State of the Watershed 16

2.1	Land-use and development	17
2.2	Existing Watershed Health and Biophysical Context	21
2.2.1	Soils	21
2.2.2	Vegetation	22
2.2.3	Wildlife	24
2.2.4	Fish and Aquatic Habitat	26
2.3	Watershed and Flood Analysis	28
2.4	Stormwater Management	31
2.5	Climate Change in the Watershed	33
2.6	Historical and Indigenous Cultural Resources	35

Community and Indigenous Engagement 37

3.1	Public and Indigenous Engagement Program	38
3.2	What We Heard	39



Recommended Actions 41

4.1	Visions for Astotin Creek Resilience	43
4.2	Vision 1: Healthy Ecosystem	45
4.3	Vision 2: Integrated Watershed Management	62
4.4	Vision 3: Resilient Infrastructure	71
4.5	Vision 4: Proactive Management	84
4.6	Vision 5: Flood and Drought Preparedness	91
4.7	Vision 6: Educated, Engaged, and Empowered Public	102

Implementation 111

5.1	Action Prioritization	112
5.1.1	Action Prioritization Methodology	112
5.1.2	Action Prioritization Results	114
5.2	Implementation Considerations	116
5.3	Funding Opportunities	119
5.3.1	Federal Funding Programs	119
5.3.2	Provincial Funding Program	123
5.3.3	Non-government Funding Programs	127

Acknowledgments 131

References 132

Appendices


A	Undersized Crossings
B	Action Prioritization Matrix
C	Project Recognition



INTRODUCTION

1





The Astotin Creek Resiliency Study is focused on building resilience within the Astotin Creek watershed. Resilience for Astotin Creek refers to the **creek withstanding and recovering from drought and flood** without the creek losing its ability to function or suffering damage **that cannot be recovered from naturally without intervention.**



The Astotin Creek Resiliency Study began with environmental and engineering assessments to understand the current state of the watershed. Results from these studies were included in the State of the Watershed and the Drainage Master Plan. The experiences and concerns of residents and other regional stakeholders have also been important components of this study. Stakeholder and Indigenous engagement occurred throughout this study and outcomes from the engagement sessions are included in the What We Heard and Did Engagement Summary Report. The Resiliency Action Plan is the final report for the Astotin Creek Resiliency Study. The Resiliency Action Plan builds on the findings from the State of the Watershed, Drainage Master Plan, and stakeholder engagement programs and includes recommended actions to improve resilience to flooding and drought. The Resiliency Action Plan includes some key takeaways and findings from previous assessments, but methodology and detailed findings are to be found in the State of the Watershed, Drainage Master Plan, and What We Heard and Did Engagement Summary Report.

There is no one-size-fits all solution for building resilience across the watershed. Instead, a combination of different actions is required to build resilience. As such, the Resiliency Action Plan is intended to provide a “tool-box” of actions that Strathcona County can use. Some actions may only be applicable in certain sections of the watershed, while other actions may be applicable at a watershed scale. Details on the applicability of actions are included within each action description. Although the County will be primarily responsible for implementation of the Resiliency Action Plan, collaboration between the County, residents, and regional stakeholders will be crucial for successful implementation. Additionally, there are some actions which have been included which can be implemented by residents, with support from the County.

The Resiliency Action Plan will begin with project context, approach, and objectives (Section 1). This will be followed by a summary of key findings from the State of the Watershed and the Drainage Master Plan (Section 2), and by key findings and outcomes from the stakeholder and Indigenous engagement programs (Section 3). A series of actions to build resilience in the watershed will be presented (Section 4), followed by considerations for implementation of the Resiliency Action Plan (Section 5).



1.1 IMPORTANCE OF RESILIENCE FOR ASTOTIN CREEK

The Astotin Creek watershed lies in the northern part of Strathcona County, in an area supporting agricultural, industrial, and rural residential land use. The watershed is within the northern end of the Beaver Hills Biosphere Reserve and forms an important link between the North Saskatchewan River valley and Elk Island National Park. This watershed is a part of a regionally significant natural area and provides important ecological goods and services, including ecological connectivity, water quality and availability. Activities undertaken along Astotin Creek can influence local and downstream conditions and so taking a holistic, watershed-scale approach to building resilience is required to ensure that actions provide intended benefits.

The current land-use and development that has occurred in the watershed provide important context for this Resiliency Action Plan. The watershed has experienced past agricultural and industrial development, clearing of riparian habitat along the creek in some areas and removal of wetlands. Both riparian vegetation and wetlands play an important role in creek health and moderation of run-off conditions. These changes to the landscape have increased flood and drought risk and reduced the overall resilience of the watershed.

Several recent flooding events (Figure 1-1) have brought considerations of water management to the forefront for Astotin Creek. The creek has flooded three times in the past decade, affecting agricultural lands, roads, and private residences. The County has responded to flood events with emergency mitigation measures such as road closures, pumping and monitoring flood conditions to protect roads, private homes, and property. These events and their associated impacts on property, infrastructure, biodiversity, water quality and quantity have prompted Strathcona County to conduct the Astotin Creek Resiliency Study. This Resiliency Action Plan will provide the County with actions to reduce flood and drought risk to ultimately reduce the costs and impacts associated with drought and flood. It is important to acknowledge that even if actions are taken to reduce risk, flood and drought risk cannot be fully eliminated. Therefore, this Resiliency Action Plan also includes actions to increase preparedness for these events.



Flooding History in Astotin Creek Watershed




Figure 1-1 Recent flooding history in Astotin Creek watershed. Historical floods recorded at the Pointe-aux-Pins Creek hydrometric station correspond to the historical floods experienced within the Astotin Creek watershed

Taking action to increase flood and drought resilience is important to reduce the risk of infrastructure damage and the associated costs and risks to public health and safety. The April 2018 flood response provides an example of the level of effort required by the County to respond to a flood event. The response required extensive deployment of County Transportation and Agricultural Services (TAS) equipment and resources to protect landowner and County property. By Tuesday April 24, 2018, the County had received reports of more than 515 culvert issues across the County, with nearly 427 resolved as of Tuesday morning (Proulx, 2018). Response efforts included:

- 2,500 sandbags laid out by Strathcona County;
- 650 tons of sand used for home protection;
- 450 feet of rapid deploy water worms, plus 26 active pumps; and
- 36 daytime TAS staff working on solutions and mitigation, and 18 nighttime workers



“...research is showing that investments in adaptation and risk mitigation measures can help ensure Canadian communities are resilient to threats caused by a changing climate, including risks to our public infrastructure. Some studies have shown a return on investment around 6:1, meaning that for every dollar invested in mitigation measures, \$6 is saved in future damages.”

- *Investing in Canada's Future: The Cost of Climate Adaptation at the Local Level, Federation of Canadian Municipalities & Insurance Bureau of Canada (2020).*




1.2 PROJECT APPROACH AND OBJECTIVES

The Astotin Creek Resiliency Study has four main objectives:

- Advance flood, drought, and water quality resiliency in priority areas within the Astotin Creek watershed to enhance the community and improve the environment;
- Restore and enhance ecological connectivity, function, and water quality in critical areas of the Astotin Creek watershed;
- Increase knowledge, awareness, and participation by industrial landowners, private landowners, agricultural producers, and citizens in activities that restore and sustain the function of the Astotin Creek watershed; and
- Enhance community capacity to restore and maintain critical features of the Astotin Creek watershed for future generations.

Resilience planning requires an interdisciplinary and cooperative approach that assesses the watershed from an environmental and engineering perspective. To be effective, resilience initiatives require the support of all stakeholders, and a good understanding of the opportunities and constraints for management. To reflect this interdisciplinary and holistic approach, the Astotin Creek Resiliency Study has been guided by “three E’s”: environment, engagement, and engineering. This study established an understanding of the watershed through a combination of environmental and engineering assessments, and stakeholder engagement as described below:





- The State of the Watershed includes the findings from a series of environmental assessments to understand the current ecological condition of the watershed. This includes soil, vegetation, wildlife, and aquatic ecosystem assessments. Findings from these studies provide information on biodiversity and habitat condition of terrestrial and aquatic ecosystems in the watershed.
- The State of the Watershed and Drainage Master Plan to include findings from engineering analysis, which describe the historical and current hydrological conditions of the creek. This includes creek flood risk, past trends, and anticipated future conditions in light of climate change projections.
- The Drainage Master Plan investigated stormwater management guidelines and infrastructure requirements to manage current and potential future levels of development.
- A stakeholder, public, and Indigenous engagement program sought input on existing conditions, issues, challenges, and opportunities within the watershed. The engagement program also solicited feedback on recommended actions from the public, Indigenous groups, and other stakeholders. Details on the engagement program are included in the What We Heard and What We Did Engagement Summary.

The recommendations in this Resiliency Action Plan respond to the findings of the **environmental** and **engineering** assessments, as well as input shared by the community during **engagement** sessions and public surveys.

To meet the objectives of the Astotin Creek Resiliency Study, opportunities for nature-based solutions have been identified wherever possible. Nature-based solutions are “actions to protect, sustainably manage, and restore natural or modified ecosystems, that address societal challenges effectively and adaptively, simultaneously providing human well-being and biodiversity benefits” (IUNC, 2019). Nature-based solutions consider the value of ecological goods and services (EGS) currently provided by Astotin Creek and seek to enhance these benefits.

Nature-based solutions not only provide co-benefits to human well-being and biodiversity, but also typically present a low-carbon alternative to traditional engineering options. Seeking to implement low-carbon solutions for flood and drought mitigation is important, as climate change is projected to exacerbate current flood and drought conditions in the future. Since nature-based solutions can reduce greenhouse gas emissions, these types of solutions help to mitigate climate change while simultaneously supporting climate adaptation.



Figure 1-2 Ecological Resiliency and Benefits through Nature-based Solutions (UCN, 2019)



STATE OF THE WATERSHED

2



The following sections **outline key findings and considerations** from the ecological and engineering assessments completed as a part of the State of the Watershed and Drainage Master Plan. These assessments included a review of relevant policies for land-use and development, ecological assessments (soil, vegetation, wildlife, aquatic ecosystem), watershed and flood analysis, stormwater management, climate change impacts, and historical and cultural resources. Additional details on methodology and detailed results of these assessments are found in the State of the Watershed and the Drainage Master Plan.

2.1 LAND-USE AND DEVELOPMENT

The Astotin Creek watershed includes a mix of developed and natural environments, including federal and provincial protected areas. Three assessment reaches were identified within the Astotin Creek watershed for this study (Upper, Middle, and Lower Assessment Reaches), in addition to the headwaters in Elk Island National Park. The assessment reaches differ considerably in their level of development, ecological and hydrological condition, and management concerns. (Figure 2-1)

Strathcona County has developed a Municipal Development Plan (MDP) and associated Land Use Bylaw (LUB) to manage land development. The MDP outlines a broad development vision across the County, with policy areas outlining permitted types and densities of development. The three MDP policy areas (Beaver Hills Policy Area, Agricultural Large Holdings Policy Area, Heartland Policy Area) within the Astotin Creek watershed, roughly match the three assessment reaches (Figure 2-1).



The LUB provides more specific guidance for future development. Land use districts mapped within the County designate specific land uses, and the bylaw outlines permitted density, setbacks, access, and building specifications. It is important to note that past development allowed within each area has also created expectations of ‘status quo’ development approaches. This plan must engage affected landowners by explaining both the rationale for adaptive changes to development approach and anticipated benefits.



Each section of the watershed has unique character and historical patterns of land use to be considered through the Resiliency Action Plan. Recommended actions include notes on applicability to specific land-uses and/or watershed assessment reaches. For example, as there have been considerable impacts from development in the Middle Assessment Reach, certain actions target this reach to improve resilience.

Upper Assessment Reach (Rural residential)

The upper assessment reach includes forested lands with rural residential and some agricultural land use (e.g., grazing). Development has been low-density, and upland habitats have experienced little disturbance or clearing.

The Upper Assessment Reach lies within the **Beaver Hills Policy Area**, created to conserve natural areas adjacent Elk Island National Park to buffer the park from more intensive land use, as part of the Beaver Hills Biosphere. Agricultural activities and low-density development can occur, including rural residential areas.

Headwaters (Natural area)

The Astotin headwaters lie within Elk Island National Park, a large federal protected



area with abundant natural habitat, biodiversity, and a Core Area of the Beaver Hills Biosphere. The Park and Biosphere both play an important role in sustaining the ecological function and benefit of the Upper Astotin Watershed, and through the creek's hydrogeological and habitat connections, its downstream reaches as well.

Middle Assessment Reach (Agricultural)

Land in the middle assessment reach has been extensively cleared for agricultural crop and pasture use. Native habitat has been retained where development was not practical, or where landowners have chosen not to clear the land. Small patches of forest remain in some upland locations and along the creek where it provides vegetated buffers of variable width along the creek edge. Wetlands have been influenced by agricultural practices (e.g., seasonal cultivation) or draining, although there are some larger wetlands, including a large reservoir (the Josephburg Reservoir), created by a weir on Astotin Creek.

The Middle Assessment Reach lies within the **Agriculture Large Holdings Policy Area**, created to help maintain the long-standing, larger scale farming operations in this area, and limit potential subdivision. Land use is intended to remain focused on agriculture.

Lower Assessment Reach (Industrial Heartland)

The lower assessment reach is largely naturally vegetated, with extensive forests and wetlands that extend beyond the watershed. Two provincial Natural Areas lie within this part of the watershed. The Lower Assessment Reach also lies within the Industrial Heartland, an area designated by the County for large petrochemical industrial developments. Petrochemical sites and facilities have been long established within this area, with supporting railway and road networks. The Lower Assessment Reach lies within the **Heartland Policy Area**. It was created to focus petrochemical industry development in an area with access to road, rail, and pipeline infrastructure. Although some agricultural land remains in the area, permitted future development includes commercial land use and new industrial projects.






Figure 2-1 Astotin Watershed - Assessment Reaches

2.2 EXISTING WATERSHED HEALTH AND BIOPHYSICAL CONTEXT


2.2.1 SOILS

The soil characteristics of each part of the Astotin Creek watershed have supported development of both its natural and human landscape. In order to understand soil characteristics throughout the watershed, previous soil mapping and studies were reviewed. The outcome of the soil assessment provided information on the types of soils, soil texture, and the resulting agricultural capability of the soils found throughout the watershed.

Key Findings:

- The **Upper Assessment Reach** has soils and terrain less suitable for agricultural use. Soils include a mixture of poorly drained soils, mainly of medium-texture (clay, clay-loam), developed on knob and kettle terrain of varied relief (Alberta Agriculture and Forestry, 2020).
- Soils in the **Middle Assessment Reach** have high agricultural capability. Terrain is undulating, with low relief and good soil texture and drainage, amenable for cereal agriculture.
- The soils of the **Lower Assessment Reach** area are varied, with a mixture of terrain and soils of higher agricultural suitability and unique terrain associated with sandy soils.
- Soil texture provides a good indication of erosion risk. Coarse to fine sandy and fine silty soils are highly erodible to wind and water erosion, while medium textured clays are less so. Soil mapping shows medium texture soils across much of the Astotin Creek watershed, with areas of fine textured soils adjacent to Elk Island National Park, and across most of the Industrial Heartland area within the Astotin Creek watershed. Coarse textured (sandy) soils extend from Fort Saskatchewan to the County boundary, along the northern edge of the Astotin Creek watershed. Small pockets of sandy soils also occur throughout the watershed, as well as localized deposits along the creek and its tributaries.





Soil characteristics provide insight to areas of higher erosion risk, which in turn can contribute to potential for sediment release to aquatic habitats. Erosion and sediment control is addressed in the Resiliency Action Plan. Soil characteristics also indicate where ecological restoration may be challenging (e.g., sandy soils) and will need to be considered when implementing actions related to ecological restoration.

2.2.2 VEGETATION


The three assessment reaches within the Astotin Creek watershed each support different vegetation communities, including native and non-native/agricultural communities. The vegetation assessment aimed to describe these communities in terms of the dominant species found in each plant community, presence of species of management concern, and types of wetlands. The biodiversity of each area was also characterized using both field survey data of species observed in different habitat types, and iNaturalist citizen science information.

Key Findings:

- Astotin Creek ranges from 5 m to 15 m wide across its channel and lies within a shallow valley with varied levels of natural and human influence on riparian habitat. The riparian buffer zone, which supports various ecological functions (e.g., water quality protection, ecological connectivity), is wider and more contiguous in the Upper and Lower Assessment Reaches. The Middle Assessment Reach has long gaps in both the 30 m and 100 m buffer zone, which has been cleared for agricultural and other human use.



- The **Upper Assessment Reach** consists of large, well connected natural habitats (riparian and uplands) with some rural, residential, and agricultural development. A few agricultural fields and pastures are present within the Upper Assessment Reach, but generally this reach is relatively undeveloped with large tracks of deciduous forest. Occasional conifer and mixedwood-dominated stands are interspersed within the deciduous stands. Large, isolated wetlands and wetland complexes are also present within the Upper Assessment Reach.
- The **Middle Assessment Reach** is dominated by agricultural development with limited native vegetation and low ecological connectivity. Cropland extends up to the riparian fringe of the creek in a large portion of the Middle Assessment Reach, which limits the native vegetation present within the riparian zone. Several small woodlands and wetlands were scattered throughout the reach. The deciduous stands were relatively small and isolated and were heavily influenced by clearing and agricultural activities in the area.
- The **Lower Assessment Reach** has some larger patches of natural habitats with moderate connectivity interspersed within cleared/industrial developed lands. This Reach is located within the northern portion of the Astotin Creek watershed where vegetation is generally characterized by jack pine mixedwood forests on sandy soils with willow-sedge wetland complexes (Spencer, 2005). Burnt areas from past fires were noted north of Range Road 560 and Astotin Creek during the field assessment. Pastures in this reach have been seeded with common agronomic species.
- One rare plant, long-leaved bluets (*Houstonia longifolia*), was identified at eleven locations in the Upper Assessment Reach. Observed populations in these locations ranged from 1 to over 200 individuals.
- Wetland mapping for the area found marsh, swamp, and open-water wetland classes across the Astotin Creek watershed area. Marsh wetlands were the most dominant wetland class across the area, with more areal extent in the Middle and Lower Assessment Reaches. Swamps were also found across the watershed but were more extensive in the Lower Assessment Reach. Some of these swamps may be coniferous swamp, or potentially peatlands. Shallow open water ponds comprised a larger area in the Lower Assessment Reach, then the Upper Assessment Reach.





A healthy riparian buffer enhances water quality, increases flood and drought resilience, and supports other ecological functions such as regional travel by wildlife and propagation of plant species. Similarly, wetlands provide multiple benefits including flood and drought resilience. Restoration and conservation of riparian areas and wetlands have been included as actions.

2.2.3 WILDLIFE

The Astotin Creek watershed lies between two areas of regionally important wildlife habitat: The Beaver Hills Moraine, and the North Saskatchewan River valley. Riparian buffers provide valuable habitat for wildlife and are critical for supporting biodiversity. Habitat along the creek and its tributaries can support movement by large mammals, such as deer and moose, as well as sustaining a variety of medium and smaller species including amphibians, mice, breeding birds, waterfowl, hawks, owls, and even carnivores like weasels and coyotes.

Semi-aquatic mammals are also common in creek and wetland habitat areas in the watershed. This includes beavers, whose dam-building can create flooding concerns, but also help sustain vegetation, wildlife and even soil moisture conditions. An understanding of ecologically important habitats and species diversity in the Astotin Creek watershed is essential to sustaining its resiliency.

The wildlife assessment included a review of previous studies to build an understanding of habitat areas, trends in habitat condition, and wildlife known to use the watershed. There was a field program to inventory wildlife in the watershed. The field program included amphibian surveys, breeding bird surveys, and remote camera surveys focused on small aquatic mammals and large mammals. An eDNA assessment was also completed to identify the presence of



four riparian carnivores based on testing at wildlife camera sites. A citizen science initiative supported the wildlife assessment which allowed citizens to share wildlife observations via the iNaturalist and NatureLynx apps.

Key Findings:

- Citizen scientist findings (using the iNaturalist nature app) returned over 3300 observations of 231 different species within the original Astotin Creek watershed area including 4 amphibian, 5 arthropod, 89 bird, 116 insect, and 17 mammal species.
- Most species observations were in the **Upper Assessment Reach**. Since the Upper Assessment Reach overlaps with Elk Island National Park, higher species observations may be linked to the rich biodiversity in the park as well as more active citizen scientists in the park area.



Actively maintaining vegetative diversity will help support diverse wildlife populations. This begins with restoring forest connectivity and riparian vegetation where land use activities have extended to the creek edge.

Management strategies can also be used to support wildlife habitat management. This includes evaluating the current protected areas within the Astotin Creek watershed, managing agricultural and industrial land use through County collaboration with private landowners, and restricting incompatible land use that leads to environmental degradation of sensitive areas.



- Results from the breeding bird, amphibian, and remote camera surveys as well as incidental observations collected during the field program provided an indication of species richness in each area of the watershed. **The Upper Assessment Reach** and **Lower Assessment Reach** were comparable at 40 species and 43 species, respectively. The **Middle Assessment Reach** had slightly lower species richness at 37 species.
- The eDNA results identified American mink at all three camera survey sites, and Northern bog lemming at the Upper and Lower Assessment Reach camera sites. American water shrew had relatively strong analysis signals at the Upper Assessment Reach site, although results for this species should be interpreted cautiously. River otter were not detected at any of the three sites.

2.2.4 FISH AND AQUATIC HABITAT

Astotin Creek and its tributaries have the potential to sustain various aquatic species. The creek and riparian wetland areas can support water birds, semi-aquatic mammals, and the aquatic invertebrate populations that, in turn, sustain them. The creek and tributaries receive waters from overland run-off, and thus can be affected by potential pollutants from human and natural sources. As a result, water quality is a key determinant of habitat quality, in addition to physical characteristics of the creek and adjacent riparian habitat. A fish habitat assessment was completed for Astotin Creek from the Astotin Creek headwaters to the downstream boundary of Strathcona County by a Qualified Aquatic Environmental Specialist, where land access was permitted. Surface water samples were also collected at five sampling points to characterize water quality relative to federal and provincial standards.

Key Findings:


- A total of six fish species have been historically documented within Astotin Creek. Most are small minnow species that are tolerant of low oxygen levels (particularly stickleback) and able to survive in shallower waters (Nelson and Paetz, 1992).
- Assessed aquatic habitat was of moderate quality for fish spawning and rearing. Habitat was assessed as moderate to good quality for migration, although it was noted that man-made weirs and perched culverts, as well



as beaver dams, may be a physical barrier for fish migration. Habitat was assessed as poor to moderate for overwintering due to the shallow depth of Astotin Creek.

- Beaver activity was evident throughout the sections of Astotin Creek accessed for fish habitat assessment. A total of 17 active dams were identified in the **Upper Assessment Reach**, 14 in the **Middle Assessment Reach**, and 6 in the **Lower Assessment Reach**.
- Water quality exceedances noted in the field samples included:
 - Fluoride exceeded the Protection for Aquatic Life (PFAL) guideline at all sampled sites but was below the criteria for agricultural land use. It is likely due to background soil conditions.
 - Total dissolved solids were just above agricultural criteria levels at one **Lower Assessment Reach** location, in a large, ponded area created by beaver damming activities.
 - E. coli was above criteria for agricultural use at two locations: slight exceedance downstream of a small subdivision area in the **Upper Assessment Reach** and double the criteria level at a site in the **Lower Assessment Reach**. This was within pasture lands leased for cattle grazing, but not currently stocked with cattle.
 - Manganese was above both the PFAL and Agriculture criteria at three locations: at the Elk Island boundary, one location in the **Middle Assessment Reach**, and in the **Lower Assessment Reach** at the downstream County boundary. Exceedances are likely linked to background conditions.
 - Slight exceedances of trace metals, including arsenic, cobalt, manganese, iron, mercury, and selenium were detected across many of the sites, but again, likely linked to background conditions rather than contamination concerns.





Aquatic health, and resiliency is determined in large part by the condition of the lands adjacent to water. An effective riparian zone is influenced by many factors including the size, topography, and geology of the watershed, which in turn affect the rate of runoff and the type of contaminants that could be introduced (ESRD, 2012). For fish bearing watercourses, a minimum 30 m riparian buffer should be maintained to help protect water quality.

2.3 WATERSHED AND FLOOD ANALYSIS

The Astotin Creek watershed lies in an area with varied terrain. This terrain has supported the development of Astotin Creek and its tributary streams, as well as wetlands and larger waterbodies, including Astotin Lake, at the creek headwaters in Elk Island National Park. The resulting hydrological network carries flows from across the watershed to the North Saskatchewan River - a relatively short direct distance but a much longer and convoluted path along the creek. The section of Astotin Creek within the County's boundaries is about 50 km long, not including its tributaries. Groundwater connections in this area are also interesting, with extensive recharge zones. Water management in this area thus must consider both surface flows and connections to underlying aquifers.

Astotin Creek flows northwest from Elk Island National Park towards Highway 15, after which the creek turns toward the northeast and eventually discharges into Beaverhill Creek, about 5 km upstream of its junction with the North Saskatchewan River. The Astotin Creek watershed at the junction with Beaverhill



Creek was delineated using topographic data, which identified a total drainage area of 184 km². Field survey of the creek mainstem (where access allowed) assessed bridge, culvert, and channel conditions.

The recent flooding events experienced within the Astotin Creek watershed were generated by meteorological events that overwhelmed Astotin Creek's flow capacity. A good understanding of the local hydrology is therefore required to understand the flood dynamic of the region. To build this understanding, a hydrological analysis was completed that included review of regional climate and streamflow data¹ to understand the driving mechanism behind the flood events experienced in the region. A flood frequency analysis, run-off model, and hydraulic modeling were also completed to better understand flood risk in the watershed.


Key Findings:

- Flood inundation maps were produced for the 100 year, 50 year, and 20 year flood events (included in the Drainage Master Plan, Appendix D). This modeling identified flood-sensitive areas along the study reach. Vulnerable areas generally consisted of overtopped roads, flooded agricultural lands, and residential lands. Flooding in these areas could generally be attributed to low-elevation floodplains and undersized crossings. The model results also suggest that part of Astotin Creek flow would leave its watershed during large flood events, spilling over into the adjacent Ross Creek watershed southwest of Highway 15. However, flood propagations outside of Astotin Creek watershed were not modeled and the entire flood flow was conveyed through Astotin Creek in the hydraulic model, leading to more conservative (wider) flood extents downstream of these outflow locations.
- The floodway for the 100-year flood was delineated where possible, and flood hazard maps were produced (included in the Drainage Master Plan, Appendix H). The simulated water velocities were also reviewed to identify reaches that are more vulnerable to erosion. Higher velocities can be expected in steeper and deeper creek sections, which are mostly located in the Middle Assessment Reach of the creek.

¹Streamflow data was not available for Astotin Creek. The Pointe-Aux-Pins Creek station is located about 20 km southwest of the Astotin Creek watershed and has similar characteristics to the Astotin Creek watershed, such as size, land use, and topography. Therefore, the Pointe-Aux Pins station is considered the most representative of Astotin Creek drainage characteristics and was used as a proxy to derive the main hydrological characteristics of Astotin Creek.



- A climate change analysis was completed to create inundation maps for a 100-year flood that incorporated a 40% increase in flow due to projected climate change impacts for a far-future high global emissions scenario² (included in the Drainage Master Plan, Appendix I).



Flood inundation maps and flood hazard maps have identified key areas to target in the Resiliency Action Plan. These areas are noted as a part of the recommended actions. Due to the variation within the watershed, **there is no one-size-fits-all solution for resilience**. Actions will include nature-based solutions, engineering solutions, and management actions, which can be used in combination throughout the watershed.

² RCP 8.5 was used in the climate change analysis. Far-future refers to a 2080 time horizon.



2.4 STORMWATER MANAGEMENT

The existing drainage system in the watershed consists primarily of drainage ways, roadside ditches, culvert crossings, privately owned and operated wet pond stormwater management facilities (SWMF), wetlands, dugouts, and depressions. The Drainage Master Plan completed as a part of this study identified issues and constraints with the current drainage system, developed a drainage servicing concept for the watershed, and identified stormwater design criteria for future development.

Key Findings:

- The number of culvert crossings (excluding private access road crossings) in the watershed is estimated to be over 100. Survey data indicated that culvert crossing pipe diameters ranged between 400 mm and 5,000 mm, including those along the creek channel. Outside of the creek channel, there are two bridge-size structures (culvert diameters greater than 1500 mm).
- Drainage patterns throughout much of the watershed generally appear to follow pre-development or natural patterns, except where modified due to the development of the transportation network. Alterations to the natural drainage patterns consist mainly of the placement of hydraulic structures across roadways (i.e., bridges or culverts) as well as straightening or realignment of portions of the creek itself and drainageways along roads.
- Drainageways are located mostly within private property, which may impede proper maintenance work and protection from alterations. Private crossings are present in some existing drainageways within private property.
- Stormwater from the agricultural lands runs off into drainageways of the creek. Stormwater from the industrial development sites is collected in privately owned and operated SWMFs for quantity control and quality enhancement. Some of the existing industrial developments retain stormwater that may not be returned to the creek. Other industrial developments release stormwater at a controlled rate into the creek only after water quality testing has been completed and approved for discharge to the creek's system. Most SWMFs include either control structures, valves, or pump stations designed to release stormwater at a maximum unit peak historical discharge rate of 4.1 L/s/ha.



- Future developments in the watershed are expected to be primarily focused on the Alberta Industrial Heartland (AIH) and comprise industrial-type developments. Based on the analysis completed, it is recommended the County adopt a 1.9 l/s/ha unit area release rate (UARR) for the watershed. While this value is lower than the current UARR (4.1 l/s/ha), it is not expected to restrict future developments. Design criteria for developments in the watershed are recommended to follow the municipal and provincial guidelines and regulations.
- A proposed drainage servicing plan was provided for the AIH lands in the watershed. The proposed system comprises a network of overland conveyance channels (i.e., ditches) and private SWMFs. Applicable stormwater best management practices for the watershed were also provided. Challenges for current and future drainage servicing in the watershed were identified and must be mitigated using best management practices.



Understanding and addressing both current and future drainage needs are important factors for flood resilience. Recommendations seek to address drainage issues identified through a variety of actions including nature-based solutions, engineering solutions, and management practices. Collaboration with landowners is crucial for maintaining and improving the drainage system in the watershed.



2.5 Climate Change in the Watershed

Increased greenhouse gas emissions are causing a long-term rise in global temperatures, which is causing changes in weather around the world. Effects of climate change are particularly notable in Canada, where warming is approximately twice the global average. This is caused by several feedback cycles such as the melting of snow and ice in high latitudes and land warming faster than oceans (Bush and Lemmen, 2019). In coming years, communities across the country will face increasing impacts that affect people, buildings and infrastructure, natural systems, and the economy.

To understand how climate change may impact flood and drought risk in the Astotin Creek watershed, an exposure assessment was completed to identify climate variables that may impact Astotin Creek. Projected changes in climate variables that relate directly to flooding (e.g., extreme precipitation) were assessed as well as those that have a more indirect influence (e.g., wildfire). Climate variables related to drought (e.g., precipitation and drought index) were also considered.



To enhance the resilience of the Astotin Creek watershed to climate change impacts, it is important to account for future climate projections in the development of flood resilience measures. For all recommended actions, including infrastructure solutions, nature-based solutions, and land-use decisions, changing climate conditions should be considered. For example, when replacing culverts, they should be sized with future precipitation projections in mind, so that they are not overwhelmed as rainfall increases throughout the century. Resulting solutions will reduce risk both in the near-term and further into the future.




Key Findings:

- An increase in mean annual precipitation is projected, which can contribute to increased creek flows and may increase the likelihood of other events causing flooding (e.g., freshet, extreme precipitation).
- Summer precipitation and maximum 5-day precipitation are projected to increase in the future. This may contribute to more frequent and severe summer flood events.
- Spring flood due to freshet is impacted by the size of snowpack and the speed at which it melts. Multiple climate parameters influence snowpack and snowmelt, and some counteracting climate trends make this hazard difficult to project. Winter and spring precipitation are projected to increase. However, snow formation could be inhibited by increases in mean winter temperature, and so snowpack size is projected to decrease over time. Mean temperatures for the spring months are projected to increase, which could result in more extreme freshet events. Spring precipitation is also expected to increase, which could also intensify freshet episodes.
- Mean annual temperature, maximum summer temperature, and minimum winter temperature are all projected to increase. The region is projected to experience more than double the number of annual heat waves³ in the long term. The length of heat waves is also expected to increase.
- While Astotin Creek has not historically been exposed to large forest fires, an increase in summer temperatures and dry, windy days could increase future occurrences. Land cover changes caused by more frequent wildfires could increase the potential for flooding.
- The number of dry days where rainfall is less than 1 mm is projected to remain stable over the century. However, the Palmer Drought Severity Index (PDSI) shows an increase in relative dryness over time. Droughts, while affecting water availability, can also have implications for the water quality in water bodies such as Astotin Creek. Drought can make the area more susceptible to intense flooding if the ground becomes hard, preventing infiltration of intense precipitation and increasing surface run off and potential for erosion and pollutant release to the creek.
- Other climate variables have the potential to impact the water quality of Astotin Creek. For example, rising water temperatures may impact habitats

³ Heat waves are a period of three-days or more when temperatures exceed 30°C.



and biodiversity through mechanisms such as the growth of harmful algal blooms. Additionally, water quality may be impacted by increased runoff during intense storms, increased sediment in runoff following a wildfire event, or increased runoff due to drought conditions.



Low-carbon resilience approaches will be prioritized where possible. A variety of actions will be required to reduce the risk of flooding from Astotin Creek in the face of changing climate conditions. However, it is important to be aware that some measures have the potential to increase greenhouse gas emissions that are driving climate change (e.g., concrete-intensive solutions), exacerbating flood risk over time. For this reason, nature-based solutions will be emphasized to further climate change mitigation and adaptation goals at the same time.

2.6 Historical and Indigenous Cultural Resources

The Astotin Creek watershed and surrounding region have seen a dramatic shift in land use over the past two centuries. This shift has brought about competing interests in the land, from Indigenous land users to a growing settler population, and later to industrial and agricultural development pressures. Balancing the needs of the people of Strathcona County, the environment, and industry continues to be a challenge today.

First Nations peoples have hunted, trapped, fished, conducted ceremony, and lived in the Astotin Creek watershed and surrounding area for thousands of years. The area's rich resources, including waterbodies, forests, open prairies, and hills provided food, shelter, and materials for ceremony (Matters and Hood 2016). The animals and plants that still make the ecosystem what it is today, such as elk, deer, moose, waterfowl, berries, and wild vegetables, provided food for the many groups that passed through the region.



The name of the moraine lands along the southern border of the watershed, amiskwaciy (Cree), or Beaver Hills, recognized the abundance of this fur-bearing mammal and its importance for Indigenous livelihood. The water systems in the watershed provided fresh drinking water, and the forests provided wood for shelter, fire, and poles used for ceremony (Matters and Hood 2016). While the landscape has changed, as has access to the land for hunting, gathering, and cultural use, Indigenous people still hold strong ties to the land today (Matters and Hood 2016), and an understanding of its ecology based in generations of past use. Those perspectives can help develop a better understanding of landscape change and resilience (e.g., gained from past periods of climate change).



The inclusion of Indigenous knowledge and perspectives in the implementation of the Resiliency Action Plan will help to enhance the narrative about the Astotin Creek watershed and surrounding area and can help to better understand land use and conservation opportunities in the region.

While many people who now live in the Astotin Creek watershed have a strong understanding of the complexities of the landscape and a strong connection to it, **Indigenous land users and knowledge holders have a unique perspective on the region**, and a deep connection to the land and water, developed over thousands of years. The meaningful inclusion of their voices will contribute to the long-term resiliency of the watershed through broadened perspectives on ecological health.





COMMUNITY AND INDIGENOUS ENGAGEMENT

3



3.1 Public and Indigenous Engagement Program

Strathcona County is committed to meaningful engagement with its residents, businesses, and neighbours. Accordingly, for this project, both public and Indigenous engagement were used to gain insights on the experiences, concerns, and management ideas for the watershed. COVID restrictions did not allow for in-person events, but outreach was possible through various existing engagement tools established by the County's Communications Team, including its SCOOP survey and eNewsletters to subscribing residents. Mail-outs with contact information and website links were sent to residents, and in August 2021, the County hosted a virtual Open House to provide early results of the environmental and engineering assessments. In November 2021, the County hosted a second set of virtual Open Houses to share information about the Resiliency Action Plan. A survey was also sent out to solicit feedback on the initial study findings, and later on the Resiliency Action Plan.

In October 2021, the County invited 31 Indigenous communities and organizations to discuss the project via one-on-one virtual meetings. Five Indigenous groups requested a meeting, during which the project was introduced and a path forward for communication was established if desired by the Indigenous group. The County is continuing these conversations with the goal of knowledge sharing and furthering relationships with its Indigenous neighbours. All participating Indigenous groups indicated they would like updates about the progress of the Resiliency Action Plan and an invitation to participate in future activities pertaining to Astotin Creek, particularly outreach or education activities and restoration activities. Overall, participating groups wanted to build stronger relationships with the County and develop pathways for ongoing communications. This feedback is represented in Vision 6, Action 4: Indigenous Relations.



3.2 What We Heard

Resulting from the first outreach initiatives in summer 2021, residents and industry identified several key areas of interest or concern: flooding, development, and the role of beavers in the ecosystem and County. These comments were used to inform the Vision Statements in the Resiliency Action Plan and are listed below.

- **Flooding:** Flooding was identified as an ongoing issue, with flood frequency seen to be increasing. Flooding was noted to be a natural process. Stakeholders noted that flooding has been seen to impact accessibility, impact agricultural lands, and noted challenges with managing flood waters.
- **Development:** Development (industrial, residential, and agricultural) has been seen to impact the creek. The condition of dams, weirs, and culverts was noted to be of concern. Concerns were also raised about the width and condition of riparian areas
- **Beavers:** Beavers were noted to be a part of nature within the watershed. Both positive and negative impacts were noted in relation to beavers. Concerns were raised related to beaver impacts and control (e.g., impacts to cattle) as well as concerns related to flooding. Positive impacts were related to water quality for cattle as for well water.

Following the development of draft Vision Statements and examples of supporting actions, another series of public engagement activities (mailouts, online survey, and virtual public engagement sessions) provided residents and stakeholders with the opportunity to provide their insight into the direction of the plan. Again, three key themes emerged from the comments received: development and infrastructure, flooding, and costs and responsibilities. These themes varied slightly from those received in the first set of engagement activities and are summarized below.

Development and infrastructure (increased and decreased development):

- Development should not be restricted beyond current bylaws (increased development)
- The Creek should be returned to a natural state and development should be restricted (decreased development)



- Connectivity of riparian areas and water flow should be maintained from the Creek source (Elk Island National Park) to the North Saskatchewan (decreased development)

Flooding:

- Flooding impacts landowners negatively and needs to be addressed
- Debris should be removed from the Creek to increase flow. Programs should include ongoing debris management.
- Engineered solutions (culvert replacement, diverting, channeling) are effective ways of dealing with flooding
- A natural creek and riparian area will flood less

Costs and responsibilities:

- Costs for resiliency actions should not be borne by landowners
- Collaboration with adjacent municipalities and parks is required
- Compensation and land buy-back programs should be cautiously explored

Overall, participants found support for the proposed Vision Statements, though participants placed higher value on different Vision Statements.





RECOMMENDED ACTIONS

4



Findings from the State of the Watershed, Drainage Master Plan, and what we heard during the stakeholder engagement sessions contributed to a series of **recommended actions to increase resilience in Astotin Creek**.

The full set of recommended actions has been developed as a **“tool-box” that provides Strathcona County with several different types of actions to address issues** throughout the watershed. This approach considers the diversity of landscapes and land uses that exist throughout the watershed. Some recommendations will apply across the watershed, while others are intended for specific geographic locations and/or only apply to certain land uses.

The applicability of each recommended action is included as a part of the action description.



4.1 Visions for Astotin Creek Resilience


As shown in the figure below, six visions were developed to represent different outcomes that will contribute to resilience in the Astotin Creek watershed.








Figure 4-1 Visions for Astotin Creek Resilience


The following table provides a summary of the visions and supporting actions. Sections 4.2 – 4.7 provide additional details on each vision and the associated supporting actions.

Table 4-1 Summary of Recommended Actions

Vision	Vision Statement	Supporting Actions
 Vision 1: Healthy Ecosystem	Astotin Creek has a healthy watershed with rich vegetation and aquatic habitat, which supports biodiversity, maintains water quality, and provides flood and drought resilience.	<ul style="list-style-type: none">V1.1 Conserve/restore vegetated bufferV1.2 Conserve/restore natural water retention featuresV1.3 Implement erosion and sediment control measuresV1.4 Implement co-existence with wildlife strategiesV1.5 Ensure aquatic connectivityV1.6 Prevent livestock from accessing creek

Vision	Vision Statement	Supporting Actions
 <p>Vision 2: Integrated Watershed Management</p>	Responsible land management within Astotin Creek watershed reduces flood and drought risk and protects ecosystems.	<p>V2.1 Conserve and restore wetlands</p> <p>V2.2 Develop land buyback and/or compensation programs</p> <p>V2.3 Maintain ecological function in Upper Assessment Reach</p> <p>V2.4 Protect and enhance drainageways</p>
 <p>Vision 3: Resilient Infrastructure</p>	Infrastructure in the Astotin Creek watershed is designed to reduce flood risk and enable adaption to climate change.	<p>V3.1 Replace undersized infrastructure</p> <p>V3.2 Elevate roads along with crossing upgrades</p> <p>V3.3 Update the allowable stormwater discharge rate for new developments</p> <p>V3.4 Incorporate flood construction level requirements in the LUB</p> <p>V3.5 Include climate change considerations in infrastructure and development standards/policy</p>
 <p>Vision 4: Proactive Management</p>	Strathcona County's programs and operations reduce flood risk in the Astotin Creek watershed.	<p>V4.1 Implement a debris management program</p> <p>V4.2 Expand asset management program</p> <p>V4.3 Proactive creek inspections and monitoring</p> <p>V4.4 Landowner education and partnership for private property clean up</p>
 <p>Vision 5: Flood and Drought Preparedness</p>	Strathcona County will invest in response planning to ensure staff and residents can deal with flood and drought events.	<p>V5.1 Develop flood response plan and training</p> <p>V5.2 Develop flood forecast, monitoring, and warning system</p> <p>V5.3 Develop a drought mitigation plan</p> <p>V5.4 Increase public understanding of flood prevention and drought mitigation, property protection and emergency response</p> <p>V5.5 Incentivize property level flood protection</p> <p>V5.6 Investigate availability of flood insurance for landowners</p>
 <p>Vision 6: Educated, Engaged, and Empowered Public</p>	Strathcona County residents will have a shared understanding of flood and drought risks and feel empowered to participate in actions to manage risks.	<p>V6.1 Implement public outreach programs</p> <p>V6.2 Implement pilot programs to showcase nature-based solutions</p> <p>V6.3 Implement citizen science initiatives</p> <p>V6.4 Indigenous relations</p>

4.2 Vision 1: Healthy Ecosystem



Healthy Ecosystem Vision Statement:

Astotin Creek has a healthy watershed with rich vegetation and aquatic habitat, which supports biodiversity, maintains water quality, and provides flood and drought resilience

Vision 1 is focused on building a healthy ecosystem in Astotin Creek. This vision recognizes the interconnectedness between the environment and human well-being. Actions supporting this vision include nature-based solutions which enhance water quality and provide flood and drought resilience.

Strathcona County recognizes the connections between a healthy ecosystem and the health and wellbeing of its residents. Strathcona County's MDP and the recently adopted Environmental Framework (2021) promote cooperative efforts to conserve and enhance the quality of air, water, land, and natural systems found in the region. This vision is directly aligned with Strathcona County's environmental objectives.

The following actions have been identified to support the vision of a healthy ecosystem for Astotin Creek. Details on each supporting action are provided in the following sections.

- **V1.1 Conserve and restore vegetated buffer**
- **V1.2 Conserve and restore natural water retention features**
- **V1.3 Implement erosion and sediment control measures**
- **V1.4 Implement co-existence with wildlife strategies**
- **V1.5 Ensure aquatic connectivity**
- **V1.6 Prevent livestock from accessing creek**





V1.1

CONSERVE AND RESTORE VEGETATED BUFFER

Description of Action

The actions required to provide a vegetated buffer along Astotin Creek will vary depending on the current condition and width of the riparian buffer, as well as existing land use/land ownership. The County recognizes the need for cooperative effort with landowners, engaged through access to existing programs and funding, and new County programs. Identifying and targeting priority areas in need of restoration will help protect the watershed as a whole. Working with landowners to maintain riparian buffers will ensure those benefits are sustained. Focus initial restoration efforts on water quality protection, riparian wildlife habitat enhancement, maintenance of habitat connectivity and implementation of a minimum 30 m riparian buffer from top of bank. These recommendations are consistent with provincial guideline documents, such as *Stepping Back from the Water - A Beneficial Management Practices Guide For New Development Near Water Bodies in Alberta's Settled Region* (ESRD, 2012), which offers a foundation of broader practice to support restoration efforts. The 30 m setback is also consistent with the land use planning process.

Specific actions could include the following steps:

- Re-establish vegetation along Astotin Creek where native vegetation buffers are less than 30 m as a first priority, ideally to a 100 m buffer to protect both water quality and biodiversity (e.g., by aiding wildlife movement).
- Promote existing ecological restoration outreach and funding programs such as the Alternative Land Use Services (ALUS), Cows and Fish, or the Green Acreages (Land Stewardship Centre) Programs to build on existing tools and funding that can help private landowners restore and maintain riparian vegetation buffers.
- Work with landowners to implement alternative land use practices that will maintain native vegetation buffers along wetland and riparian areas (e.g., rotational grazing programs, off-stream watering stations, weed management). These could be offered through County workshops, or in



partnership with existing programs such as ALUS, Cows and Fish or the Land Stewardship Centre.

- Limit removal of intact riparian native vegetation in the Upper and Lower Assessment Reaches to maintain connectivity between Elk Island National Park, the two Natural Areas and the North Saskatchewan River Valley (e.g., through County development policy or bylaws). Focus at a minimum on the creek buffers and consider opportunistic conservation of ‘stepping-stone’ habitats where extensive, larger habitat patches exist near the creek (e.g., through conservation easements).
- Identify and implement conservation measures required to protect known rare plant populations within the watershed, and particularly where present on County lands (e.g., the long-leaved bluets (*Houstonia longifolia*) identified in a County owned, former sand pit area). These populations can serve as sources for natural propagation, particularly if ecological connectivity is maintained.

Benefits

The riparian area serves multiple purposes for Astotin Creek including bank and shoreline stability, improved water quality, provision of habitat, as well as providing a buffer for flood resilience. Vegetation can anchor soils adjacent to stream, preventing erosion of banks during flood and severe storm events. Vegetation buffers can also filter out sediments that may be carried in overland surface flows into the creek. Such measures are particularly important in sandy areas, which are more susceptible to erosion. Vegetated riparian areas can also buffer drought effects, by reducing evapotranspiration effects. The vegetation, particularly if left ungrazed in early spring (i.e., with rotational grazing), prevents evaporative loss from the underlying soils.

Applicability

This action applies to the entire watershed, but particularly to the Middle Assessment Reach where riparian vegetation has been removed up to the creek edge (both along the mainstem and smaller tributary areas) and riparian intactness was much lower than in the rest of the watershed.



Cost

Restoration costs would mainly address seed and seedling plants, and costs of County outreach support. Similar programs have been used by rural municipalities in the past, providing seedlings to land owners who sign-up with a description of their restoration plans. Costs would be relatively low, depending on uptake. Various funding options can be made available, either through County-wide programs such as the ALUS program, or through site-specific funding offered through organizations such as the Land Stewardship Centre's Green Acreages program. The new federal initiative to reforest lands in partnership with municipalities (2 Billion Trees Program) offers another potential funding source.

The ALUS program relies on local advisory committees formed from interested agricultural producers and landholders, which offers advantages for promotion and support for program delivery, as well as locally relevant advice on restoration methods and funding. Additionally, the County could partner with non-profits such as Cows and Fish or Agroforestry & Woodlot Extension Society (AWES) to support outreach initiatives for management of riparian areas. Their programs are tailored specifically to agricultural landowners and emphasize benefits relevant to sustainable agricultural activities.

"Cows and Fish is non-profit society striving to foster a better understanding of how improvements in grazing and other management of riparian areas can enhance landscape health and productivity, for the benefit of landowners, agricultural producers, communities and others who use and value riparian areas."

"Since its creation in 1992, Cows and Fish has delivered presentations, field days and workshops to over 92,200 people across Alberta and Canada."

— (Cows and Fish, 2021).





V1.2

CONSERVE AND RESTORE NATURAL WATER RETENTION FEATURES

Description of Action

Flood attenuation can be provided by the natural capacity of wetlands and adjacent flood fringe lands to capture and slowly release water back to the creek system. These same features can also provide drought resilience by storing water, particularly if riparian vegetation is left intact. Potential conservation and restoration areas include wetlands and flood fringe zones along the main Astotin channel, but also tributary drainages that comprise the headwaters of the creek. They, and other wetlands throughout the watershed, will hold back flood waters in very wet years, attenuating flood events, but also sustaining soil moisture in the adjacent lands through shallow groundwater flows. In drought years, these areas can sustain soil moisture and open water longer, particularly if vegetation cover is maintained within and immediately adjacent to wetlands and the creek. Riparian vegetation helps to reduce evaporative loss, holding soil moisture longer than cleared lands.

Specific actions to help conserve and restore natural water retention features, including headwater drainage channels and wetlands both adjacent the creek and tributaries, and in the uplands include the following:

- Conserve and enhance wetlands in off-channel (in adjacent uplands) and near channel (within the riparian buffer) habitats to hold water during high precipitation years and dampen flooding intensity. This can include avoiding cultivation through smaller, more temporary wetlands near the creek edge or in the flood fringe zone or maintaining larger permanent wetlands in upland and riparian areas. The County's existing Wetland Conservation Directive generally covers wetland loss and could be expanded to address cultivation and drainage of wetlands in agricultural areas.
- Implement wetland restoration through use of provincial funding associated with the County's Wetland Replacement Program. Working with interested landowners, identify potential restoration sites within the Middle Assessment Reach in particular, where wetland loss has been most dramatic.



- Through existing programs such as Cows and Fish, or the ALUS program, promote alternative land management strategies in agricultural areas to help maintain healthy vegetation cover adjacent to riparian areas. Healthy, dense vegetation cover can help prevent evaporative loss to sustain soil moisture during drier periods; native cover species are also more resistant to drought than most introduced species.

Benefits

Retention of wetlands and flood fringe zones adjacent to the creek channel can provide additional flood storage, and mitigate peak flood flows, as well as enhancing aquatic habitat and species diversity. In drought years, healthy vegetation in these areas can reduce evaporative loss, helping to sustain open water and soil moisture for agricultural and ecological benefits.

Applicability

Wetland conservation in upland and flood fringe areas can be applied throughout the watershed, while restoration efforts should focus on the Middle Assessment Reach, where land clearing has been most extensive. Areas where the riparian buffer has been cleared, or where riparian wetlands have been cultivated in dry years would provide more immediate and tangible demonstration of flood attenuation, and ecological benefits, and could serve as demonstration or pilot project areas. These areas would also have less impact on agricultural operations, and thus better potential uptake by landowners. Restoration and replacement of upland wetlands would have similar effect, and could also be pursued with willing landowners, but the lack of direct connection to the creek obscures the relationship to reduced run-off, and flood flows. To build program support, pilot projects along riparian areas may have more impact.

Cost

Delivery of public awareness programs could be completed in conjunction with partnering organizations, or alternatively through County staff outreach activities. Restoration efforts should focus on the Middle Assessment Reach, both through opportunistic, site-specific wetland restoration efforts (e.g., through delivery of provincial wetland restoration projects, funded by provincial wetland compensation), and through outreach programming to shift land management practices.



ALUS is an agriculturally focused program that promotes sustainable land management, working in cooperation with local landowners and producers. “ALUS partnerships help build vibrant communities by implementing the program through a Partnership Advisory Committee (PAC) made up of local farmers, community stakeholders and other NGOs. This allows each community program to address specific local environmental challenges and work collaboratively towards implementing sustainable solutions. ALUS provides financial and technical support for the implementation of these projects and annual payments to its participants to ensure the ongoing stewardship of each of their ALUS projects” (ALUS, 2021).





V1.3 IMPLEMENT EROSION AND SEDIMENT CONTROL MEASURES

Description of Action

Uncontrolled stream erosion can lead to undesirable bank migration impacting private and public lands. Stream erosion typically occurs at fast-moving water sections where the bank and riverbed are unprotected. Excessive erosion can impact water quality and aquatic species by increasing the water turbidity. The eroded material is transported downstream and deposited in the creek's flatter and slower flow sections, where the sediment transport capacity is reduced. Excessive sedimentation can also have undesirable effects by elevating the creek bed elevation, which increases water levels upstream of these deposition zones. The hydraulic simulation results suggested that the Middle Assessment Reach is more prone to erosion, given the higher water velocities along the steeper creek slopes. However, the prevalence of beaver dams in this section of the creek reduces the water velocities and the bank erosion potential. Several mitigation measures can be implemented to address site-specific erosion problems, such as:

- Bank hardening (riprap)
- Bio-engineering stabilization (wattles, brush mattress, branch packing, live crib wall)
- Floodplain restoration

Bank hardening measures generally consist of placing unerodable materials, such as stones (riprap), along the eroded section of a stream. Riprap can be placed longitudinally along the bank or transversely (spurs bendways) to direct stream flow away from the eroded banks. Bio-engineering stabilization methods use vegetation to restore the bank and improve its erosion potential.

Riparian enhancement and site-specific bank stabilizations will also help address the increased sediment inputs from the lack of a riparian buffer. Consider unique soils in ecological restoration. Sandy areas that occur in pockets across the watershed will have faster water infiltration rates than areas of fine to medium texture. Ecological restoration in these areas will require different planting



mix and methods, including selection of drought resistant species. Selecting revegetation species and planting methods appropriate to local soil drainage, flooding patterns, and moisture conditions (including drought-resistance) will help ensure good vegetation catch and sustainable growth. Native species are often better adapted to regional flood and drought cycles than non-native species and will be a better choice for restoration.

Benefits

Implementation of sediment control measures improves bank and stream stability and limits bank migration, improving water quality. Bio-engineering stabilization methods can also restore floodplain riparian areas and improve habitat diversity. Erosion control measures also reduce sediment transport, limiting excessive sedimentation and potential stream obstruction.

Applicability

Erosion and sediment control measures should be implemented where excessive erosion has been noted (e.g., adjacent undersized culverts or bridges). Regular inspection programs, including the debris clean-up along the creek can help identify candidate sites. Bio-engineering stabilization should be prioritized in sections of the creek where bank migration does not pose a significant risk to landowners and public infrastructure. Bank hardening techniques should be used at high-risk location where roads and infrastructure are located close to the creek. A mix of bioengineering and bank hardening techniques can also be implemented to provide robust and green stabilization upgrades.

Cost:

Cost of erosion and sediment control measures can range from \$1000 to \$5000 per linear meter depending on the type of control measure.





V1.4

IMPLEMENT CO-EXISTENCE WITH WILDLIFE STRATEGIES

Description of Action

The proximity of Elk Island National Park and the North Saskatchewan River valley at either end of the Astotin Creek watershed helps to sustain watershed and regional biodiversity, which means watershed residents will encounter a greater variety of wildlife than in more developed areas. While some species are appreciated, others, such as beaver and large carnivores, are often considered nuisance or risk species. Others are not typically noticed, yet play significant ecological roles (e.g., pollinators). Collectively, biodiversity provides important ecological and human benefits that are sometimes overlooked, but expensive to replace through engineered solutions. Co-existence strategies can help ensure these species, and their benefits are sustained. Such strategies rely firstly on a shared understanding of benefits, as well as means to minimize negative effects, or in some cases, compensate landowners for adverse impacts.

Learning to Live with Beavers



Beaver have been extirpated in Britain for centuries, and are only now being reintroduced as part of watershed restoration. Often such programs use outreach to build program support, and pro-actively address potential human-beaver conflicts.

Auster et al. (2021) assessed one such program, providing recommendations to reduce conflict and promote co-existence:

- Proactive engagement or a fast response for potential issues;
- Appropriate lines of communication;
- Shared decision-making;
- Foster a sense of the role of humans in beaver conflicts;
- Address need for certainty through proactive planning.



Co-existence strategies to address the negative impacts, or sustain the benefits of wildlife species include the following:

- Develop public outreach programs to raise awareness of the presence of wildlife and the benefits of co-existence. Species such as beaver and large carnivores that were extirpated from many areas during early settlement have either re-established in this area (e.g., beaver) or are returning due to loss of habitat in other areas (large carnivores). For some landowners, these species may be ‘new’ relative to memories of earlier generations on the land, and yet they are filling important ecological roles pre-dating settlement of this area. Removal of species well adapted to this landscape, like beaver, will be costly, since recolonization from adjacent habitat will be on-going and long-term. Co-existence will be less expensive and provide other ecological benefits, like sediment capture, water storage and support of higher biodiversity.
- Consider innovative tools to foster co-existence with beavers. Although beaver activities along Astotin Creek are thought to cause flooding and other damage that create human-wildlife conflicts, they can also provide a variety of ecological benefits. Alternative management techniques such as ‘beaver deceivers’, pond levellers and similar devices can control flood damage while still allowing beaver to remain on the landscape. Promoting such solutions for co-existence through outreach has been successful in other jurisdictions (Auster, et al., 2021), and is consistent with the objectives of the Environmental Framework.
- Working with affected landowners, develop new, innovative methods such as compensation for land flooded by beaver, to help sustain beaver ponds in strategic locations (e.g., within high priority habitat units, or as ‘stepping stones’ along the creek to maintain ecological connectivity), or areas where recolonization by beaver is likely (e.g., near Elk Island National Park, or in the Industrial Heartland). The ALUS program and federal initiatives for climate adaptation may offer means to fund compensation.
- Track wildlife-human conflict (e.g., with beaver and large carnivores) particularly in areas adjacent to Elk Island National Park and the North Saskatchewan River. Consider implementation of programs such as ‘Bear Aware’ to avoid creating attractants (e.g., garbage, compost piles) or to promote deterrent measures and alternatives to avoid beaver impacts



on private lands (e.g., beaver deceivers, pond levellers, exclusion fencing), and emphasize the ecological and human benefits of beavers. Additional innovative programs could be developed with affected landowners proactively to address emerging concerns, through community advisory groups established through other programs (e.g., through the ALUS program, which involves landowners in ecological restoration planning).

Benefits

The benefits of beavers include helping to maintain water on the landscape during drought, as well as moderating floods and erosion effects by holding back water and sediment behind dams. Higher soil moisture resulting around beaver ponds also offers a natural protection from wildfire (Fairfax and Whittle, 2020). Other benefits include improvements to water quality by retention and breakdown of nutrients and capture of naturally occurring contaminants (e.g., metals) in less hazardous forms within pond sediments. Ecological benefits include promoting biodiversity, from aquatic invertebrates and amphibian species through to waterfowl and ungulates. These species in turn can help control pest species (e.g., insects), and support other services such as pollination. Large carnivores can help regulate populations of other wildlife species (e.g., ground squirrels, deer, and beaver), as well as providing aesthetic wildlife viewing opportunities for residents and visitors to the area.

Applicability

Co-existence programs would apply across the watershed, but particularly in areas near Elk Island National Park and the North Saskatchewan River. Such areas may support more abundant populations of perceived nuisance species, and adjacent landowners may have more frequent issues.



Cost

Outreach could be supported through County staff, or in partnership with groups such as Cows and Fish and the Miistakis Institute (e.g., for beaver management alternatives). Alberta Parks and Elk Island National Park have all implemented alternative beaver management programs and have also developed large carnivore awareness and prevention programs. These agencies are affiliated with the Beaver Hills Biosphere, which could help facilitate collaborative program delivery in the watershed. The Beaver Hills Biosphere is currently undertaking a project focused on coexisting with wildlife. Future outcomes from this project could help to inform strategies for co-existence with wildlife. Finally, pond levelers and exclusion fencing are relatively inexpensive to install (\$1000 to \$2000/site for materials) and require limited maintenance (see the Miistakis Institute information [here](#)).

Beavers and Climate Resilience

A recent study in Washington State evaluated the capacity of beaver re-introductions to buffer drought effects of climate change (Dittbrenner, 2019).



Reintroductions in the Skykomish area, in the Cascade Mountains found surface water storage increased by 243 m³ /100 m of stream in year one, and stored and additional 2.4 times more groundwater. Downstream water temperatures were 2.3 C cooler in summer, which helped reduce evaporative loss.

With climate projections of reduced snowfall in this area, beavers were estimated to increase summer water availability by 20% - a considerable ecological and human benefit.






V1.5 ENSURE AQUATIC CONNECTIVITY

Description of Action

The State of the Watershed highlighted the need for aquatic connectivity to prevent flood conditions through adequately sized and debris-free culverts. Aquatic connectivity can also provide ecological benefits by facilitating access to habitat for aquatic and semi-aquatic species and maintaining diverse aquatic habitats. This in turn provides human benefits such as reducing nutrients in downstream systems, pollination, and insect controls. Some judgement is required for implementation of these actions: not all debris is necessarily a barrier. Trees and logs carried downstream along the channel can provide ponded and riffle habitat and hiding cover for aquatic and semi-aquatic wildlife, as well as shading to reduce evaporative loss. Even beaver dams allow a small trickle of flow, and travel overtop or through the impoundment by aquatic, semi-aquatic, and terrestrial species. Natural creek flows have a mixture of ponded (flat) and flowing (riffle and run) habitat, each of which supports different plant and wildlife species. Riparian vegetation buffers can also indirectly support connectivity by reducing evaporative loss and thus, sustaining flow.

Connectivity can be maintained by both engineering and nature-based solutions and would best be implemented in cooperation with landowners along the creek. Recommended actions for the creek and its tributaries include the following:

- Removal of physical barriers to improve aquatic connectivity. Examples of barriers include perched culverts (outlet suspended above water), debris jams at culverts and bridges, high weirs, and fencing across the creek that can capture debris. Aim for removal of barriers that will obstruct both animal movement and water flow, on both the mainstem of the creek and its tributaries.
- Replace undersized culvert and bridge crossings. Undersized crossing structures constrain flows, which can result in upstream flooding. Smaller crossings also increase the velocity of flow through them, which can prevent upstream access for some species (e.g., frogs, minnows) and create stream erosion issues downstream.



- Develop a community awareness program with information on the types of obstructions that pose a risk, human and natural barriers to flow, and characteristics and benefits of a healthy and connected aquatic system.
- Monitor debris accumulation at culvert and bridge crossings, particularly after large storm or flood events. Monitoring could be done by residents through a citizen science program coordinated by the County. This approach would provide proactive monitoring support and help raise local awareness of the types of barriers they could control on their own lands (e.g., fencing, undersized culverts).

Benefits

Improved aquatic connectivity will reduce flooding, but also help to sustain biodiversity and increase resilience throughout the creek, in terms of habitat and species. Diverse aquatic communities will play a role in controlling water quality, as well as supporting other services supported by the riparian edge (e.g., habitat for pollinators and insectivorous birds). Aquatic vegetation, riparian vegetation, and other micro-organisms in the water (e.g., bacteria) both take up nutrients carried in creek water, helping to ‘clean’ water of inputs (e.g., fertilizer, manure) contributed from overland flows.

Applicability

Aquatic connectivity actions apply across the watershed. One perched culvert was identified during field surveys at 54511 RR 204 crossing (south of Hwy 15). Undersized crossings are listed in Vision 3.

Cost

Programming to support a citizen science or public information campaign could be supported by the County, or in collaboration with Cows and Fish or ALUS programming. Debris removal and culvert or bridge replacement would mainly be funded through County programs.





V1.6

PREVENT LIVESTOCK FROM ACCESSING CREEK

Description of Action

While streams, wetlands and other waterbodies have long been used to provide water for livestock, open access can have detrimental effects on water quality and quantity, as well as habitat conditions. Manure and ‘potholing’ around the riparian edges created as cattle access water can introduce nutrients and sediment, as well as pathogens (e.g., bacteria like *E. coli*). Grazing often occurs around the riparian edge too, since soil moisture promotes lush grass growth, but ironically, overgrazing can cause drought conditions in later summer, due to evaporative loss. Maintaining off-stream watering stations can alleviate these problems, as can riparian edge fencing to restrict grazing at certain points of the year. Cost-benefit studies of alternative water sources have found cattle do better as well – cattle weight gain has been found to be higher with a watering system, rather than dug-outs or stream access (Canfax, 2018). The improved water quality enhances palatability, and better cattle hydration. A rotational grazing pattern in riparian areas helps ensure good vegetation cover over the spring and summer months, which helps sustain year-round stream flow and good grazing conditions later in summer.

Specific actions related to livestock access management include the following:

- Install an off-stream watering station (e.g., solar-powered pump/trough system) that provides better access for livestock to water. Ideally, a watering station would be combined with fencing along the riparian edge to restrict access to the stream and grazing lands near the creek, as part of a rotational grazing system.
- Allow areas that have experienced past grazing to recover through vegetation growth for an appropriate period, then implement rotational grazing in these areas.
- Combine access management with restoration of riparian vegetation (planting of native grasses or shrub stakes) to help restore riparian vegetation cover. This will help reduce evaporative loss from the creek and sustain stream flows through drier periods.



- Develop a community awareness program to build understanding of livestock impacts on riparian areas and provide information on livestock management options to reduce impacts.

Benefits

Reducing inputs of nutrients, sediment and other contaminants will improve water quality in the creek for participating landowners, and downstream users. Improved water quality will also improve aquatic and riparian habitat conditions, supporting other ecological services and human use.

Applicability

These actions would apply on any lands currently used for livestock grazing, including leased lands.

Cost

Costs include solar-powered watering systems and fencing materials, which can be supported through the ALUS system (should the County chose to adopt it), or the Green Acreages Program. Units can range from \$9,565 for a solar powered pumping system, to \$13,274 for a windmill system, plus costs for pipe (Canfax, 2018) . Federal and provincial watershed protection grants have periodically sponsored such activities, and the County could also apply for grant funding on behalf of interested residents.



4.3 Vision 2: Integrated Watershed Management



Integrated Watershed Management Statement:

Responsible land management within Astotin Creek watershed reduces flood and drought risk and protects ecosystems.

Land use and development are important considerations for resilience. Flood and drought resilience needs to be considered on a watershed scale to ensure that actions taken in one area of the watershed do not have negative upstream or downstream impacts. Providing areas for water storage and protecting ecosystems are both important to build resilience to flooding and drought.

Policy and programs related to land-use and development are tools that can be used to guide future development, as well as create opportunities for restoration to enhance resilience.

The following actions have been identified to support the vision of integrated watershed management for Astotin Creek. Details on each supporting action are provided in the following sections.

- V2.1 Conserve and restore wetlands
- V2.2 Develop land buyback and/or compensation programs
- V2.3 Maintain ecological function in Upper Assessment Reach
- V2.4 Protect and enhance drainageways





V2.1 CONSERVE AND RESTORE WETLANDS

Description of Action

Wetlands, both within the creek flood fringe and in the uplands across the watershed play an important role in flood risk by holding back surface flows after snowmelt and storm events. They also help to sustain soil moisture in these same areas, through infiltration into the adjacent soils in shallow groundwater flow. Wetland vegetation takes up nutrients entering the wetland through surface flows, improving water quality before release through shallow groundwater flow. Retaining intact wetlands is critical to supporting these benefits, including temporary and seasonal wetlands that flood mostly in spring or rain events, as well as open water ponds. Creating a shared understanding of the diverse types of wetlands, and their ecological benefits will help support conservation and habitat enhancement efforts. Lastly, the County's role in the provincial Wetland Replacement Program could help replace or enhance existing wetland habitat.

Actions to support wetland conservation in the watershed include:

- Encourage retention of wetlands, particularly in the flood fringe zone (e.g., in development proposals).
- Limit new development within the Upper Assessment Reach to maintain wetland habitat, ideally with a minimum 30 m wide buffer. Policy updates to stress avoidance of wetland loss could strengthen existing policy tools (e.g., including development incentives for proposals that avoid and protect wetlands or requiring local replacement, rather than compensation payment, by developers).
- Seek locations for wetland restoration in collaboration with interested private landowners to identify sites proactively for inclusion into the Wetland Replacement Program.



- Encourage land management practices that can help maintain and sustain wetlands (e.g., avoid cultivation within the 30 m buffer, or within temporary and seasonal wetlands). Working with conservation partners to deliver outreach programs can build on existing materials, experience and delivery approaches for agricultural and rural residential programming (e.g., Land Stewardship Centre, Cows and Fish, Miistakis Institute).

Benefits

Wetlands can help take up flood flows and help sustain water availability through drought conditions, as well as providing water quality improvements, and enhancing habitat and biodiversity.

Applicability

Wetland conservation can be done across the watershed. Wetland restoration efforts should focus on the Middle Assessment Reach, where loss has been higher, and specifically on the riparian flood fringe, which would affect crop cultivation less.

Cost

Delivery of public awareness programs could be done in conjunction with partnering organizations, or alternatively through County staff outreach activities. Wetland restoration activity is funded by provincial wetland compensation.





V2.2 DEVELOP LAND BUY-BACK AND/OR COMPENSATION PROGRAMS

Description of Action

Certain jurisdictions in Alberta have recently resorted to deliberate overland flooding to temporarily divert and/or store flood water to reduce peak flows and flood risk downstream of these locations. This sometimes leads to temporary flooding of agricultural and recreational lands, which can adversely impact landowners. Temporary storage of flood water on large agricultural areas can significantly reduce flood flows and flood risk downstream. This flood management approach typically includes a Flood and Compensate model, providing payment for economic losses due to flooding.

The recent floods on Astotin Creek revealed that several agricultural lands are located within the floodplain and are at risk of flooding. While this is detrimental to certain landowners, overland flooding can have a beneficial effect on downstream flood risk by temporarily storing a large amount of water and reducing downstream flood flows. Any attempt to contain the creek flow at these locations, through dikes and channelization work, would reduce floodplain storage and potentially increase flood risk downstream. Such measures also require on-going maintenance, adding to overall cost. A potential flood management approach would be to tolerate overland flooding, to reduce downstream flood risk, and compensate the impacted landowners for their agricultural losses. For example, significant overland flooding was noted during the 2018 flood between Range Road 212 and Highway 15 in the Middle Assessment Reach. A Flood and Compensate program would compensate the landowners for crop loss based on the total area of impacted land, negotiated between the County and the landowners using current market rates. It should be noted that all-risk crop insurance is also available to farmers in every province through The Crop Insurance Act, enacted in 1959. Historically, the Canada-Alberta Excess Moisture Initiative II (CAEMI II) provided \$30 per eligible acre to producers with land too wet to seed as of June 20, or for land already seeded which lost crop due to flooding. Although this program is not in place anymore, the Agricultural Financial Services Corporation (AFSC) now provides a suite of crop insurance programs which offer protection against crop losses from designated perils, such as flooding and drought.



Land buyback is another alternative, which gives owners the option to move away from flood areas and reduces the amount of physical property potentially impacted by flood events. Strategic acquisitions of natural and undeveloped parcels can also be done to preserve the floodplain from future developments. This approach was recently implemented in Sainte-Marie-de-Beauce, in Quebec, where over 200 properties located within the Chaudière Rivière floodplain were purchased and demolished in 2020.

Benefits

Floodplain protection through a land buyback or compensation program conserves the floodplain integrity and allows for flood storage and peak flow attenuation. Land buybacks also decrease the extent of potentially impacted homes and physical infrastructure and future flood recovery costs.

Applicability

Land buybacks and compensation programs can be implemented over the entire floodplain, with a focus on the Middle Reach.

Cost

Land acquisition costs are highly variable but are estimated at about \$100,000 per hectare of land. Crop compensation costs vary with market values. Current cereal crop value is about \$1000 per hectare.





V2.3 MAINTAIN ECOLOGICAL FUNCTION IN UPPER ASSESSMENT REACH

Description of Action

The Upper Assessment Reach has largely retained native forest and grassland cover, due to constraints imposed by morainal terrain. As a result, surface flows are well filtered through vegetated areas, evaporative loss is lower and flood attenuation is provided by wetland storage. This part of the watershed thus supports downstream flows in both quality and quantity, and in both wet and dry years. Conserving these naturally vegetated areas as much as possible will help moderate the severity of floods and drought on downstream areas.

Policy and conservation tools will help to maintain ecological function in the Upper Assessment Reach area:

- Review and update land use planning policies to ensure specific references to conservation priorities such as wetlands, riparian buffers, floodplains and creek tributaries are protected, as a minimum consideration for future development proposals. Smaller tributaries and temporary or seasonal flood duration wetlands, in particular, are not necessarily linked to conservation requirements in agricultural use nor residential development policies.
- Promote riparian land management practices through County outreach activities, or in collaboration with environmental organizations already active in this area of practice (e.g., the Land Stewardship Centre, Cows and Fish, Miistakis Institute).
- Work with local landowners to establish conservation easements along the length of the 100 m riparian buffer lands through the Upper Assessment Reach area to help protect the headwaters and water supply for downstream areas and provide flood attenuation.
- Protect parcels with high environmental value (e.g., known species at risk, wetlands) through conservation land purchase, as opportunities arise.



Benefits

Maintaining ecological function of the lands in the Upper Assessment Reach will help protect water quality, sustain downstream flows (especially in drought), and buffer flood and storm events through wetland and flood fringe storage. Such protective measures will also help sustain ecological connections with Elk Island National Park and within the rest of the Beaver Hills Biosphere, as well as associated ecological benefits.

Applicability

Applies to new development in the Upper Assessment Reach, which are addressed in part under the Beaver Hills Policy Area requirements in the MDP. The Policy Area currently places limitations and obligations on agricultural, residential and commercial landowners. Some are specific, such as development of an Environmental Farm Plan to promote responsible human – environment interactions and limitations on structures or land use, while others more generally require consideration of environmental impacts. More explicit protections for land management around wetland and riparian lands could be added to the MDP and LUB to protect riparian buffers (for example) or limit forest clearing for operational (as opposed to structural development) land improvements.

Cost

Updates to MDP and LUB can be done through regular administration and Council approval processes. Conservation easements or land purchase could be held by the County, or other environmental organizations active in this area (e.g., Ducks Unlimited, the Edmonton Area Land Trust, Nature Conservancy of Canada). Land costs in this area will dictate purchase costs (currently about \$100,000 per hectare). The Land Stewardship Centre, Cows and Fish, and the Miistakis Institute have prepared various educational materials that provide advice on riparian management that could be distributed through the County as part of outreach programs (e.g., Stepping Back From Water).





V2.4 PROTECT AND ENHANCE DRAINAGEWAYS

Description of Action

Runoff in the watershed is conveyed to Astotin Creek through overland flow collected in drainageways that are primarily located within private property. In the Middle Assessment Reach, such areas have been cultivated through, removing all vegetation buffers and the benefits they provide (e.g., reducing evaporative loss and enhancing filtration). In the Upper and Lower Assessment Reaches, vegetated buffer areas may remain, but they can be at risk to future development. To protect these lands from alteration and aid in restoration, the County could pursue easement or drainage right-of-way acquisition along key drainageways. Another alternative is to develop conservation buffer zones for key drainageways through modifications to existing land use policy (e.g., within the LUB), as a strategy to promote riparian health throughout the watershed.

Benefits

Implementation of this vision would aid in conserving or restoring vegetated buffer zones. More practically, an easement would allow the County access to complete maintenance activities such as removal of sediment, debris, and trash, and repair of hydraulic structures along key drainageways. This vision also offers some degree of protection from alterations to drainageways that help sustain flows or provide flood attenuation (e.g., through riparian wetlands or flood fringe lands).

Applicability

This vision is primarily applicable to the agricultural lands in the Middle Assessment Reach immediately south of Highway 15.

Cost

Easement or right-of-way acquisition costs are highly variable. An estimated range would be \$15,000 or \$25,000 per hectare of land. Land use policies that protect a buffer on tributary drainageways would have no land purchase costs, but would require public outreach to secure buy-in.



Quebec Magpie River ‘rights of the river’.

In February 2021, Quebec broke new legal ground by establishing ‘rights of a river’. Two parallel resolutions, one by the Innu Council of Ekuanitshit, the other by the regional government of Minganie grant the river nine rights – including the right to live, exist and flow; the right to respect for its natural cycles; and the right to take legal action. This action mirrors other international examples ranging from New Zealand to India, that seek to establish the same protections against harm currently granted to people and corporations.

Hessey, 2021



4.4 Vision 3: Resilient Infrastructure



Resilient Infrastructure Vision Statement:

Infrastructure in the Astotin Creek watershed is designed to reduce flood risk and enable adaption to climate change

Infrastructure plays a critical role in maintaining quality of life in Strathcona County. To ensure infrastructure continues to function as designed and serve the community, it is crucial that County infrastructure is resilient. Actions supporting this vision seek to identify and address issues with existing infrastructure as well as guiding resilient design for new infrastructure. When designing and developing new infrastructure, flood risk and climate change are both important considerations. As climate change is anticipated to impact flooding in the future, infrastructure should be designed with future climate in mind to build long-term resilience.

The following actions have been identified to support the vision of resilient infrastructure for Astotin Creek. Details on each supporting action are provided in the following sections.

- V3.1 Replace undersized infrastructure
- V3.2 Elevate roads along with crossing upgrades
- V3.3 Update the allowable stormwater discharge rate for new developments
- V3.4 Incorporate flood construction level requirements in the LUB
- V3.5 Include climate change considerations in infrastructure and development standards/policy





V3.1 REPLACE UNDERSIZED INFRASTRUCTURE

Description of Action

The hydraulic modeling simulations for the creek revealed that several crossings (bridges/culverts) are undersized for large flood events, thereby increasing upstream water levels and leading to wider flood inundation zones. This was expected, given that most crossings on small local roads are generally designed for smaller flood events than the 100-year flood in Alberta. Hydraulic design of crossings in Alberta are generally based on the basin potential and channel capacity analyses, combined with a reduction factor provided in Alberta Transportation's Hydrotechnical Design Guidelines for Stream Crossings (AT, 2006). For low volume local roads, these hydrotechnical calculations typically lead to a smaller design flow than the 100-year flood. Given that the watershed area increases further downstream along the creek, the design flow and hydraulic opening of the crossings should increase as well. However, this is not the case for Astotin Creek. A wide range of hydraulic openings was measured at crossings along Astotin Creek, moving from Elk Island National Park to Lower Assessment Reach, as shown on Figure 4-2.




Figure 4-2 Hydraulic opening of surveyed crossings along Astotin Creek

Some of the smallest culverts along Astotin Creek were found in the lower section of the creek, about 35 km downstream of Astotin Lake, despite draining a larger watershed area than upstream crossings. For example, RR 212, shown on Figure 4-3 (a), comprises three culverts with diameters of 920 mm, 1200 mm, and 780 mm respectively, for a combined hydraulic opening of 2.3 m². In comparison, the CN bridge, shown on Figure 4-3 (b) and located about 10 km upstream of RR 212, has a hydraulic opening of 60 m², which is about 25x bigger than the crossings at RR 212. The CN bridge and the RR 210 bridge have the two highest hydraulic opening along the study reach, whereas the other crossings generally have a hydraulic opening of 20 m² or less. The culverts at Highway 15 have a hydraulic opening of about 20 m².



Figure 4-3 a) Culverts at RR 212 b) CN bridge, downstream of Highway 15

When replacing existing structures, bridges and open bottom culverts (arch culverts) should be favored over culverts as they can provide a greater discharge capacity and provide better hydraulic connectivity for aquatic species. Several crossings located on private lands were also identified along Astotin Creek, but their dimensions could not be surveyed due to access restrictions. Some of these crossings are located just downstream of residential and agricultural lands and could promote overland flooding if they are not adequately designed. Although upgrading crossings on private lands falls outside of Strathcona County's jurisdiction, landowners should be made aware of potential consequences of installing undersized creek crossings and encouraged to consult with the County when installing or changing crossings along Astotin Creek. Such an outreach program could be incorporated into existing agricultural extension programs offered under the County's Agriculture Master Plan.

Benefits

Replacing existing crossings with larger structures would bring the following benefits:

- Reduced blockage risk
- Increased discharge capacity, reducing upstream water levels and flood risk
- Reduced erosion and scour downstream
- Reduced likelihood of road overtopping
- Improved stream connectivity and fish passage

Applicability

Although upgrading all Astotin Creek crossings by bridges that can accommodate the 100-year flood is not economically practical, it is recommended to upgrade specific crossings located in flood-prone areas. Based on the hydraulic simulations, the following crossings, also shown on maps in Appendix A, were found to be undersized and promoting overland flooding. Replacement should be considered first at these sites:

- RR 204 (SW33-54-20-4)
- RR 205 (SW32-54-20-4)
- RR 210 (NW31-54-21-4)
- RR 210 (NW6-55-20-4)
- RR 212 (SW2-56-21-4)
- TR 550 (NW32-54-21-4)
- TR 552 (NW-11-55-21-4)
- TR 560 (NE33-55-21-4)
- TR 560 (NE34-55-21-4)

Replacements of the culverts at TR560 (NE33-55-21-4 and NW34-55-21-4) should be prioritized as it considerably impacts upstream flood levels, which could promote overland flooding in the Industrial Heartland. The other crossings identified in Appendix A and listed above also increase upstream flood risk for landowners, but their length of influence upstream is more limited, given the



steeper longitudinal slope of the creek. The bridge at RR 210 directly impacts the flood levels for the landowner of SW6-55-20-4 and should be prioritized. Site-specific hydrotechnical studies should be conducted at each site to determine the most appropriate crossing size and opening when considering local topography, constructability, aquatic connectivity, and flood risk. As further detailed in the following vision (V3.2), raising roads that currently can get overtopped during large flood could increase the flow being conveyed through culverts and bridges. Future road upgrades should be taken into account when completing site-specific hydrotechnical study for crossing upgrades.

Although closed-bottom culverts are generally cheaper and easier to install, clear span and open bottom structures (bridges) offers many advantages over culverts, such as:

- Greater discharge capacity due to greater hydraulic opening.
- More resistance to erosion during large flood events if the abutments are well armored.
- A natural stream channel in continuity with the natural stream.
- Improved aquatic connectivity by reducing water velocities compared to culverts which improves fish passage.

Certain types of open-bottom culvert types can offer similar advantages to bridges such as arch culvert as well as embedded closed-bottom structures. The choice and design of crossing structures on a fish-bearing stream are determined by a number of factors, including sensitivity of fish habitat, cost, fluvial geomorphology and topography. A site-specific approach should be implemented when determining which structure type should be used to replace existing crossings.

Cost

Cost for crossings upgrades depends on the size and type of the new structures. Recent work completed by Strathcona County suggest that replacement cost of existing crossings can range from \$50,000 to \$1,000,000 per project.





V 3.2 ELEVATE ROADS ALONG WITH CROSSING UPGRADES

Description of Action

Road overtopping was reported at several locations within Astotin Creek watershed during the 2018 flood. The hydraulic model confirmed that several local roads would be overtopped during large flood events. Road overtopping can be attributed to undersized crossings and low points along the road. For instance, RR 213 was overtopped over a significant length during the 2018 flood. The hydraulic model showed overtopping at the same location, which correspond to a low point of the road according to the LiDAR elevation data, as shown on Figure 4-4. Raising the road elevation at such sites would prevent road overtopping and improve transportation connectivity during large flood events.

The hydraulic model also suggests that the overtopped section of the road convey a significant portion of Astotin Creek flow for large flood events. For the 20-year flood, the modeled flow overtopping RR 213 accounted for nearly 40% of the total Astotin Creek flow and 60% was conveyed through the bridge. Raising RR 213 above flood levels would increase the flow to be conveyed by the bridge, which would lead to higher water levels upstream of RR 213 compared to current conditions.

In other words, raising roads without increasing the crossing's discharge capacity could increase flood risk upstream of the upgraded roads. The existing bridge/culvert discharge capacity should be considered when raising a road susceptible of overtopping along Astotin Creek.






Figure 4-4 (LEFT) RR 212 overtopped during the 2018 flood event (b) Hydraulic modeling results of the 20-year flood.

Benefits

Raising roads above flood levels improves connectivity and emergency response during flood events. It also reduces the flood-related damages to infrastructure and improves post-flood recovery. Raising the roads at low points would, however, increase the flow through the crossings, which could increase upstream flood levels if the crossing is undersized. It is important to consider the crossing's current discharge capacity when raising roads at risk of overtopping to avoid unintended flooding impacts. Combining road raising with an upgraded crossing could be required at some locations where the current culvert or bridge is undersized.

Applicability

The hydraulic model identified the following roads, also shown on maps in Appendix A, as being potentially overtopped during large flood events:

- 54511 RR204 (SW33-54-20-4)
- RR 204 (SW33-54-20-4)
- RR 205 (SW32-54-20-4)
- RR 210 (SW31-54-20-4)
- RR 210 (SW6-55-20-4)
- RR 211 (SE11-56-21-4)
- RR 212 (Multiple locations)
- RR 213 (Multiple locations)
- RR 214 (Multiple locations)
- TR 550 (NW36-54-21-4)
- TR 552 (NW11-55-21-4)
- TR 553 (upstream of HWY 15)
- TR 560 (Multiple locations)
- TR 562 (NE12-56-21-4)
- TR 554 (NW21-55-21-4)

Upgrading some of the crossings identified in V3.1 would reduce the frequency and magnitude of overtopping at the roads listed above and roads upgrades might not be required if the new crossings are sufficiently large. Potential road upgrade works should therefore be analyzed in combination with crossings upgrades to determine if roads should be raised above their current elevation.

Cost

Cost for road upgrades depends on the length and the depth of fill required to reach the desired crest elevation. Recent work completed by Strathcona County suggest that cost of road upgrades can range from \$500 to \$1,000 per linear meter of road upgrades.





V 3.3 UPDATE THE ALLOWABLE STORMWATER DISCHARGE RATE FOR NEW DEVELOPMENTS

Description of Action

Hydrologic analysis of the Astotin Creek watershed indicated that the pre-development unit area release rate (UARR) is 1.9 l/s/ha for the 100-year flood event. Future developments in the County's Industrial Heartland within the Lower Assessment Reach where there is greater potential for intense development should adopt the pre-development UARR for the design of stormwater management best practices. The UARR is applicable to the Upper and Middle Assessment Reaches as well.

Benefits

The intent of adopting the pre-development UARR is to maintain or replicate natural hydrological conditions after development has occurred, by requiring peak flow attenuation. This in turn minimizes the impact to downstream water and land resources. More specifically, adoption of the pre-development UARR protects Astotin Creek by:

- Mitigating large peak runoff rates, which can in turn impact the downstream water and land resources.
- Mitigating creek streambed and bank erosion.
- Mitigating the delivery of pollutants to the creek.

Furthermore, hydraulic assessment of the creek channel and instream hydraulic structures (culverts and bridges) indicated that capacity is limited. The pre-development UARR can help address capacity issues and thus allow for smaller hydraulic structures.



Applicability

This vision applies to all areas of the watershed that will undergo development. Currently, the County's planning documents indicate that future developments requiring stormwater management are anticipated to occur in the Industrial Heartland area within the watershed.

Cost

Costs associated with this action are anticipated to be minimal and internal to the County.



V 3.4 INCORPORATE FLOOD CONSTRUCTION LEVEL REQUIREMENTS IN THE LUB

Description of Action

Raising finished floor levels within a development is an effective way of avoiding damage to the interior of buildings (i.e., furniture and fittings) in times of flood. A Minimum Building Elevation (MBE) effectively mitigates flood risk damage to new buildings and allows for people to recover more quickly after a flood event. Modifying ground levels to raise the land above the design flood level is a very effective way of reducing flood risk to a particular site, in combination with other measures such as emergency response planning. Figure 4-5 shows how raising a building can reduce physical property damage.



Figure 4-5 MBE effect on physical property damage

Although new developments in the flood fringe might be acceptable (e.g., if development in the flood fringe does not increase upstream flood levels by more than 0.3 m) the first floor of new developments (including the building's electrical and mechanical equipment) must be constructed at or above the design flood level. The flood fringe corresponds to the portion of the flood hazard area outside of the floodway, where flood water is generally shallower and flows more slowly, as shown in Figure 4-6.




Figure 4-6 Illustration of the floodway and flood fringe.

If new developments are to be allowed within the flood fringe, Strathcona County's LUB could be updated to require a minimum building elevation for new developments along Astotin Creek. Geotechnical evaluations already required for subdivision development, for example, could incorporate recommendations for flood proofing for development in the flood fringe. The minimum building elevations are site-specific and should include sufficient freeboard (0.6 m is recommended) above the legislated flood level. Existing structures in good condition can sometimes be elevated on extended foundation walls or on compacted fill to raise the level of the first floor above the MBE. Raising existing buildings above flood construction levels is, however, an expensive endeavor and actions proposed in other visions may be more economically effective.

Benefits

Flood construction levels greatly minimize the flood damage for future developments within the floodplain. They ensure that living spaces and areas used for the storage of goods are kept above flood levels.

Applicability

Flood construction levels would be applicable to any new development within the Astotin Creek floodplain.

Cost

There is minimal cost to implement policy changes. There is an increase in construction cost to build homes above MBE, however, these additional costs are expected to be largely compensated by reduced flood damages.



V 3.5 INCLUDE CLIMATE CHANGE CONSIDERATIONS IN INFRASTRUCTURE AND DEVELOPMENT STANDARDS/POLICY

Description of Action

To build infrastructure resilience to climate change, climate change considerations can be integrated into standards and policy related to infrastructure design and land development. This includes the addition of language to consider climate change when developing design criteria for new infrastructure. For example, when designing stormwater infrastructure, future rainfall projections should be considered in infrastructure sizing. At a minimum, climate projections should align with the infrastructure's design life. For infrastructure with a design life of 50 years or more, climate projections for the 2080 time-horizon should be considered.

It is also important to consider climate change for development within the floodplain. The 1:100-year flood plain is typically considered for future development and is referenced in the LUB and the provincial Municipal Government Act Subdivision Regulation. While this restriction has been long-standing in municipal land use policy, adaptations to consider climate change have not. Consistent application of these policies, and incorporation of steps to consider climate change risks will ensure that development within the floodplain incorporates appropriate adaptation measures for flooding.



Climate change science is an evolving discipline and ongoing monitoring of climate science and trends is important to understand and respond to climate risks. Climate risk assessment and response planning should be an ongoing exercise for the County and requirements for infrastructure and development should be adjusted as required over time to address climate risk.

Benefits

Infrastructure designed to withstand climate change will not only provide required services today but will continue to provide reliable services and safe operations in the future. Climate resilient infrastructure design contributes to overall community resilience and helps to manage and mitigate climate change risks. Taking action to integrate climate resilience during infrastructure planning and design prevents the need for early replacement or retrofits to adapt to a changing climate.

Applicability


This recommended action applies to all County policies, standards, and regulations that govern infrastructure design and development. This includes, but is not limited to, the LUB, stormwater design guidelines, and culvert design requirements.

Cost

There is minimal cost to implement policy changes. Costs to design to future climate may increase, however, investing in infrastructure resilience is anticipated to have long-term cost benefits by preventing future damages.



4.5 Vision 4: Proactive Management



Proactive Management Vision Statement:


Strathcona County's programs and operations reduce flood risk in the Astotin Creek watershed.

This vision is focused on actions that the County and landowners can take on a regular basis to reduce flood risk in Astotin Creek. Programs and operations that focus on the early identification of issues will allow for timely action to remedy these issues before they become significant. Although it is intended that the County take a lead on the actions within this vision, as private land extends to the Astotin Creek edge throughout the watershed, partnership and collaboration with landowners will be important for the successful implementation of recommended actions. Landowners can be directly involved in supporting this vision through initiatives on their land as described within the supporting actions.

The following actions have been identified to support the vision of proactive management for Astotin Creek. Details on each supporting action are provided in the following sections.

- V4.1 Implement a debris management program
- V4.2 Expand asset management program
- V4.3 Proactive creek inspections and monitoring
- V4.4 Landowner education and partnership for private property clean up





V4.1

IMPLEMENT A DEBRIS MANAGEMENT PROGRAM

Description of Action

During a site visit completed in June 2021 by WSP, some natural and anthropogenic features were recognized that might reduce the carrying capacity of the creek and cause ponding issues at several locations. Some examples of these features are illustrated on Figure 4-7 and listed below:

- Beaver dams under or downstream of crossing structures
- Woody debris along the creek and especially at the upstream end of small culverts
- Piles of woody debris along the creek (naturally washed out or manually removed from the channel and stacked in the floodplain)
- Human made obstacles (e.g., fences crossing the creek) .

A debris management program (e.g., annual debris removal) should be developed to keep the channel clear, especially at bridge and culvert crossings. The debris management program can include removing beaver dams located close to crossings and flood risk areas, wood jams, dead trees and shrubs, and silt accumulation at the entrance of crossings. Debris accumulation is highly dynamic and evolves rapidly year over year. The debris management program should therefore be complemented by proactive site inspections, as described in Vision 4.3.

Benefits

Regular debris removal and channel clearing helps to improve the creek's flow conveyance capacity, reduce the risk of local flooding and erosion, and maintain the creek's natural beauty.



Applicability


Debris removal is mainly applicable to the upstream parts of the creek with natural conditions (e.g., the Upper Assessment Reach). However, annual investigation and cleaning is recommended around all the crossings and wherever overland flooding has been noted. Only major debris blockage, as shown on Figure 4-7, should be cleared along the creek. Small accumulations of woody debris should be left undisturbed as they generally do not cause conveyance problems and provide other habitat and stabilization roles.

Cost

Under most circumstances, debris removal expenses are relatively low and are limited to the cost of labour unless heavy machinery is needed.



Figure 4-7 Examples of excessive debris accumulation and manmade barriers noted along Astotin Creek



V4.2 EXPAND ASSET MANAGEMENT PROGRAM

Description of Action

Municipalities are increasingly tasked with tracking maintenance and replacement costs of infrastructure, including culverts and bridges. Many have turned to asset management systems that can track infrastructure specifications and age, as well as maintenance and performance issues, to assist in capital and operational budgeting. In some cases, such information has clarified or supported assumptions regarding long-term performance, informing future planning expectations, as well as budgeting. An asset management program that tracks culverts and bridges, plus other associated infrastructure (road repairs, alternative beaver management installations) can help with future planning and budgeting. Strathcona County currently manages select assets through the Bridge and Bridge Culvert Replacement Program which includes bridge culverts with a diameter of 1.5m or greater. Pedestrian bridges are not included in the current program. It is recommended that Strathcona County expand on this existing program to include all drainage infrastructure in the watershed.

Recommended actions for an expanded asset management program include:

- Creating an inventory of current assets, with age, condition, and replacement costs (if known). This initial inventory provides the starting point for future tracking, and ideally is linked to locations through a GIS spatial layer. The Bridge and Bridge Culvert Replacement Program does include a GIS layer, however, at this time asset information is not linked to location.
- Tracking on-going maintenance costs and timelines over the lifespan of the infrastructure. This information will inform future replacement timing, and operational budgeting. The Bridge and Bridge Culvert Replacement Program already tracks and records costs, and so this process could be replicated in an expanded asset management program.
- Completing regular inspections and include a complaint tracking log tied to each asset for use in monitoring maintenance issues, repairs, and other condition updates. The system, once established as a baseline can



be used to forecast annual maintenance, replacement, or upgrading costs. The Bridge and Bridge Culvert Replacement Program already includes inspections by certified bridge inspectors following Alberta Transportation's Bridge Inspection Manual. Inspections inform replacement planning and prioritization of work based on condition and available budget. Additionally, the current program is building a deterioration model and confirming expected service life of assets based on experience and data verification. The systems in place for the Bridge and Bridge Culvert Replacement Program can be built upon in an expanded asset management program, with tailored inspection requirements for different types of assets.

Benefits

By tracking the installation costs and specifications, condition, maintenance, and repair of all drainage infrastructure in the watershed, future maintenance and replacement can be better forecast, based on actual performance records. For innovative solutions such as beaver pond levelers, data can be compared to traditional management costs to 'prove the concept'.

Applicability

Ideally, an asset management program would include all drainage infrastructure in the watershed (i.e., all culverts and bridges), plus any stormwater or other control infrastructure, including alternative beaver management installations. Tracking would exclude the two bridge-sized culvert structures owned and managed by Alberta Transportation.

Cost

An asset management program can be developed using existing County personnel and GIS systems. Some additional funding may be required (e.g., to cover cost of inspections and/or additional time required to set up an expanded asset management program), but may be eligible for grant funding. Costs associated with inspections and condition ratings for some assets are already included in County budgets through the Bridge and Bridge Culvert Replacement Program.





V4.3 PROACTIVE CREEK INSPECTIONS AND MONITORING

Description of Action

Action 4.1 highlighted the importance of maintaining adequate flow conveyance at flood-prone locations. To avoid excessive debris accumulation, Astotin Creek should be inspected annually. Annual inspections would also help identify other undesirable concerns such as:

- Bank and channel erosion;
- Damages and blockages at bridges and culverts; and
- New beaver dams in flood-prone areas (e.g., at culvert and bridge sites).

Results of the annual inspection should feed into the debris management program (V4.1) to schedule clean-up. The annual inspection report should also identify concerns that should be addressed such as bank repairs or bridge and culvert maintenance or replacements. Annual inspections should be carried out following the spring freshet or any major storm events to identify potential issues arising from increased flow.

Benefits

Proactive creek inspections would provide valuable information regarding the creek's integrity and would help identify areas of concern that should be addressed. It would also provide a clearer picture of the creek's current condition and help budget required capital work.

Applicability

Recognizing that inspecting the entirety of Astotin Creek would be time consuming, focus the inspection activities at the bridge and culvert crossings and at the flood-prone areas identified in Appendix H of the Drainage Master Plan. Recruiting resident support for a volunteer survey on private lands could provide information on debris accumulation in these areas.

Cost

Costs associated with this action are anticipated to be minimal and internal to the County.





V 4.4

LANDOWNER EDUCATION AND PARTNERSHIP FOR PRIVATE PROPERTY CLEAN UP

Description of Action

Several culvert crossings and sections of the creek are located on private lands and are not readily accessible to the County's staff. A community approach to the Astotin Creek cleanup could be implemented by the County. Astotin Creek residents could be encouraged to 'adopt a reach' of Astotin Creek where they would help monitor, clean and maintain the creek on their lands. This could either be carried out through individual, continuous activity or through annual creek cleanup events organized by the County. Landowner education would be required to highlight the impact of debris blockage on flood risk, and the types of blockage that need to be removed. The debris management program could be shared openly to any landowner motivated to take part into the cleanup effort. Note that timing of the clean-up activity should avoid times where impacts to wildlife might occur (e.g., during spring bird breeding season, fall beaver and amphibian hibernation periods), particularly if water draw-down may result.

Benefits

Partnerships with landowners would foster collaboration and promote individual involvement in the flood mitigation effort. This would also promote 'ecological literacy' and help develop a shared understanding of a healthy creek environment.

Applicability

This action applies to the entire watershed and would be relevant to landowners adjacent to Astotin Creek. Creek clean-up events could also include other County residents who would like to get involved in activities to improve flood resilience for the community.

Cost

Costs associated with this action are anticipated to be minimal and internal to the County.



4.6 Vision 5: Flood and Drought Preparedness



Flood and Drought Preparedness Vision Statement:

Strathcona County will invest in response planning to ensure staff and residents can deal with flood and drought events.

Although the Resiliency Action Plan seeks to reduce flood and drought risk, it is also important to prepare for flood and drought as risk cannot be fully eliminated. Supporting actions within this vision seek to build an understanding of how to respond to flood and drought events. These measures aim to ensure health and safety, while protecting infrastructure and reducing damage.

The following actions have been identified to support the vision of flood and drought preparedness for Astotin Creek. Details on each supporting action are provided in the following sections.

- V5.1 Develop flood response plan and training
- V5.2 Develop flood forecast, monitoring and warning system
- V5.3 Develop a drought mitigation plan
- V5.4 Increase public understanding of flood prevention and drought mitigation, property protection, and emergency response
- V5.5 Incentivize property level flood protection
- V5.6 Investigate availability of flood insurance for landowner





V5.1

DEVELOP FLOOD RESPONSE PLAN AND TRAINING

Description of Action

Although flood events are somewhat unpredictable in nature, emergency response procedures should be clearly defined, and operating staff well trained to manage a flood emergency in an organized and coordinated manner. The flood response procedures should be outlined in a specific plan that documents the actions that operations staff are to follow in the event of a flood. The plan should include the key emergency response roles and responsibilities, in order of priority. The response plan should also include the following:

- Flood response levels based on streamflow and meteorological data;
- Notification procedures, including contact information for key emergency roles;
- Notification chart of all residents living within the flood inundation zone;
- A list of preventive and remedial actions;
- Flood inundation maps; and
- Location and availability of equipment, emergency power sources, contractors and stockpiled materials that are critical to the emergency response.

The flood response plan is not a one-off activity, but rather a living document that needs to be revisited and reassessed as the community grows and changes. The plan also needs to be practiced through mock flood events and examined for effectiveness after a flood event.

Benefits

A flood response plan will enable a swift, effective, and efficient response, which can limit flood damage and accelerate recovery.



Applicability

This action is applicable for the entire Astotin Creek watershed.

Cost

The cost to develop a flood response plan is estimated to be about \$50,000 and annual training is estimated at about \$5,000.



**V5.2 DEVELOP FLOOD FORECAST,
MONITORING AND WARNING SYSTEM**

Description of Action

Data on flood flows and levels are essential to understanding when and where extreme river flows and levels might occur and to inform flood risk management measures. Similarly, recording details of flood events is extremely useful to build knowledge of flood risk throughout the community and to understand flooding patterns. This can also help to calibrate the computer models used to predict potential future flooding. The ongoing collection of flood-related data is a measure that will help to continually improve preparation for, and response to flooding.

It is possible to forecast floods using weather predictions, observed rainfall, observed snowpack, and predicted temperature. River levels and flows then can be predicted using hydrological models. Flood forecasting involves significant uncertainty, as it entails simulation of very complex systems in real-time with limited data which may result in false alarms. Alternatively, streamflow can be monitored in real-time to determine rate of water level rise and potential upcoming flooding. Streamflow monitoring combined with flood thresholds can be used to develop flood alert levels.

Some flood monitoring strategies follow a three-level approach, as shown in Table 4-2. Each warning level explains the level of risk and demonstrates the actions that need to be undertaken. A flow value is typically associated with each alert level, which is triggered when the flows measured at monitoring stations exceed these thresholds. These flood thresholds should be clearly defined in the Flood Response Plan described in V5.1.



Table 4-2 Example of flood alert levels

	<p>Flood alert - Prepare</p> <p>Check flood warnings/updates regularly. Ensure vulnerable people are aware and prepare their vital possessions and prescriptions.</p>
	<p>Flood warning - Act</p> <p>Prepare for a potential flood, contact vulnerable people, move valuables to safe zone, watch flood alerts for potential evacuation.</p>
	<p>Severe flood warning - Evacuate</p> <p>Evacuate to safe area.</p>

Benefits

Having a flood forecast and warning system in place helps people to act appropriately and mitigate risk. Knowing that a flood event is impending allows people in the community to prepare for the flood, for example, by moving people, furniture, and valuables away from the incoming floodwater. Streamflow monitoring would also provide valuable streamflow data at Astotin Creek that can be used to refine the hydrological and hydrotechnical analyses completed as part of this study. Citizen participation in monitoring rainfall and stream flow, in addition to County run stations, can help engage residents in flood preparedness, and provide a broader network of monitoring stations.

Applicability

The flood forecast, monitoring and warning system would apply to the whole Astotin Creek watershed and its residents. Flow monitoring stations should be installed at locations where the creek is well confined to ensure that the station captures the entirety of the flow. Figure 4-8 shows a potential location for hydrometric station installation, in quarter-section SW12-55-21-4, where Astotin Creek is well confined and streamflow monitoring would be possible. Any other locations where Astotin Creek is well confined and where overland flooding is limited would be suitable sites to install a hydrometric station.




Figure 4-8 Potential hydrometric location

Cost

\$25,000 to \$50,000 per streamflow monitoring station, depending on the sophistication level of the installed instruments. Rain gauges and simpler stream gauges could be provided to residents at low cost and data acquisition could be supported through County resources (e.g., online or phone reporting).



V 5.3 **DEVELOP A DROUGHT MITIGATION PLAN**

Description of Action

As noted by the National Drought Mitigation Centre (2021), drought planning should seek to:

- Identify water-dependent functions of the community;
- Prioritize water-dependent functions; and
- Determine steps to adapt those functions if water supplies begin to drop.

Undertaking an exercise to understand the impacts of drought on the Astotin Creek watershed is the first step to building drought resilience. Looking at water needs for residential, industrial, and agricultural water users will help to build this understanding. It is also important to consider fire risk and ecosystem impacts from drought. Establishing the priority of water uses, and the steps that will be taken to reduce water use and/or seek alternate sources of water are both important components of drought preparedness. A drought response plan should be developed for the Astotin Creek watershed that includes the prioritization of water uses and adaption plans.

The American Planning Association has developed guidance on Planning and Drought that provides additional aspects of drought planning. Important components of drought planning include monitoring and early warning, vulnerability assessment, and mitigation actions. Many drought plans also incorporate a phased response, which outline different actions to be taken as drought conditions intensify. The importance of community engagement to support drought planning is also noted. (Schwab, 2013)

Benefits

Understanding the impacts of drought for the watershed and developing response and mitigation plans will help to County and residents to adapt in the event of a drought.



Applicability

Drought preparedness will apply to the entire watershed.

Cost

Internal costs for staff time and resources.



V 5.4

**INCREASE PUBLIC UNDERSTANDING OF
FLOOD PREVENTION AND DROUGHT
MITIGATION, PROPERTY PROTECTION,
AND EMERGENCY RESPONSE**

Description of Action

Flood and drought risk management is a shared responsibility between the County and private landowners. The public needs to understand how to prevent flooding through their activities in the watershed, protect their property in the event of flood and drought and how to behave in an emergency situation. Effective risk communication and associated action requires that all participants have a common understanding of risk, understand their role in risk management, and feel empowered to act. The Partners for Action's Community Guide to Effective Flood Risk Communication (MacKinnon et al., 2018) recommends a series of steps to develop a risk communication plan:

1. Understand the community's perception of risk via two-way communication and consultation.
2. Create localized communications that include community-specific values, stories, and tangible examples of risk.
3. Link local stories, actions, and examples to a broader strategy, goals, or messaging, such as nation-wide impacts of climate change, or national/regional flood and drought mitigation strategies.
4. Communicate the responsibilities (and limitations) of public authorities relative to individual response, using the context and communication



pathways established in the previous steps.

5. Monitor the effectiveness of the communication plan and identify areas for improvement and update the process as necessary.

Benefits

Prepared residents are better able to participate in the County's emergency response processes and will be safer and better able to respond to an emergency event. Informed residents can actively participate in preventative actions to reduce flood and drought risk, working with County administration.

Applicability

Communicating risk response and preparedness will apply to the entire watershed.

Cost

There is little to no capital cost to establishing a public outreach campaign, but staff time and resources will be required.



V 5.5

INCENTIVIZE PROPERTY LEVEL FLOOD PROTECTION

Description of Action:

Property level flood protection (PLFP) is any measure that helps a property owner reduce flood damage without adversely affecting neighboring properties. Some examples are grading property away from the house, removing expensive items from the basement, installing weeping tiles, elevating electrical/HVAC equipment above flood levels, installing a sump pump, using water-resistant material, and building dykes to protect vulnerable infrastructure. Figure 4-9 provides various PLFP and their adoption rates in Canada, according to a 2016 survey (Thislethwaite et al. 2018). Note some of these PLFP are more efficient against sewer backups than overland flooding.






Figure 4-9 Various property level flood protection measures and their adoption rate in Canada (Thislethwaite et al. 2018)

Local governments can promote PLFP uptake through various economic and bylaw interventions. For example, Toronto's Basement Flooding Protection Subsidy Program offers up to \$3,400 per property for installing a backflow prevention valve or sump to protect against flood. Similar incentives could be implemented by the County to promote PLFP uptakes by residents located within the Astotin Creek floodplain.

Benefits

Implementing property level flood protection measures reduces the impact of floods on people and their property and allows for a faster flood recovery.

Applicability

The property level flood protection measures are applicable to all the owners with a property in a floodplain, especially those with a residential house in or close to the floodplain.

Cost

PLFP cost can range from minimal for removing expensive items from basement to costly, such as floodproofing a property with water resistance materials. PLFP cost are generally covered by landowners but as mentioned previously, local governments can also implement economic incentives to favor PLFP uptake. Federal and provincial climate resiliency grants may also support such incentives, providing a potential funding source.



V5.6

INVESTIGATE AVAILABILITY OF FLOOD INSURANCE FOR LANDOWNERS

Description of Action

Flood coverage is one of the most complicated aspects of home insurance in Canada and few insurers were offering overland flooding coverage until recently. But as of 2019, about 80% of Canadians had access to some form of overland flood insurance. Most insurers now offer optional overland flood coverage, which covers losses from damage to home, condo or personal property. But despite more accessible flood coverage, market penetration for overland flood insurance was still below 40% as of 2018 and coverage in high-risk areas was either unaffordable or not readily available. A National Working Group on Financial Risk of Flooding, co-chaired by Public Safety Canada and the Insurance Bureau of Canada (IBC), has been recently implemented to develop a new insurance model in Canada that would promote affordability, inclusivity, and efficiency. The shift towards a risk financing approach rather than a public disaster recovery approach is still relatively new and rapidly evolving. As overland flood insurance becomes more available and accessible to landowners, Astotin Creek owners located within the floodplain should consider acquiring optional overland flood coverage to mitigate the financial impact of a flood event.

As mentioned in Action V2.2, all-risk crop insurance is also available to farmers in every province through The Crop Insurance Act, enacted in 1959. More specific to Alberta, the Agricultural Financial Services Corporation (AFSC) provides a suite of crop insurance programs which offer protection against crop losses from designated perils, such as flooding and drought. Lands that are subject to repeated flooding or where excess moisture is a recurring problem may not be insurable, at the discretion of the AFSC.

Benefits

Provides landowners with financial support following a flood and spreads the risk among policy holders. Personal flood insurance also decreases reliance on governments to support financial reparation following a flood event.

Applicability

Applicable to any landowners located within the Astotin Creek floodplain. Insurance coverage availability should be confirmed with insurance brokers. As new policies become more available, the option can be included in County flood preparedness information for residents. County GIS mapping provides means to identify relevant landowners, including those immediately adjacent the creek.

Cost

Applicable to any landowners located within the Astotin Creek floodplain. Insurance coverage availability should be confirmed with insurance brokers. As new policies become more available, the option can be included in County flood preparedness information for residents. County GIS mapping provides means to identify relevant landowners, including those immediately adjacent the creek.



4.7 Vision 6: Educated, Engaged and Empowered Public



Educated, Engaged, and Empowered Public Vision Statement:

Strathcona County residents will have a shared understanding of flood and drought risks and feel empowered to participate in actions to manage risks.

Flood and drought resilience will require both County action and involvement from residents throughout Strathcona County. It is important that residents understand risks related to flood and drought as well as opportunities to contribute to risk reduction efforts. This vision supports the realization of the other five visions in the Resiliency Action Plan as public support and involvement will be crucial for the success of numerous supporting actions.

The following actions have been identified to support the vision of an educated, engaged, and empowered public for Astotin Creek. Details on each supporting action are provided in the following sections.

- **V6.1 Implement public outreach programs**
- **V6.2 Implement pilot programs to showcase nature-based solutions**
- **V6.3 Implement citizen science initiatives**
- **V6.4 Indigenous Relations**





V 6.1

IMPLEMENT PUBLIC OUTREACH PROGRAMS

Description of Action

Several of the previous visions included public outreach programs to inform and empower residents to participate in flood and drought preparedness and risk reduction. Examples include support to ecological restoration actions for a healthy ecosystem, information on natural creek systems to support debris removal in the creek, and information on wetland conservation. Emergency preparedness is another area where public involvement will be critical. In some cases, outreach will provide additional context to develop shared understandings of an issue, in others, outreach will provide information, ideas and resources to allow landowners to undertake projects to support creek resiliency and protect their own property from flooding and drought impacts. Partnering with existing organizations who have these materials and delivery mechanisms already established may be helpful (e.g., working with Cows and Fish, the Miistakis Institute, and the Land Stewardship Centre to deliver workshops or provide information). Some outreach would be better coordinated through the County, to provide local context and more direct insight into management decision processes. In all cases, outreach should aim to engage, inform, and empower residents and stakeholders, and provide the County with feedback on local interests and capacity to adopt recommended management plans.

Benefits

Flood and drought resiliency is necessarily a collaborative process involving landowners and municipal administrators. Moving toward shared understanding of issues and the applicability of management solutions will ensure implementation of cost-effective and timely solutions, and allow for active participation of residents and other stakeholders. Strathcona County has an existing public engagement policy and various tools for public outreach (website, newsletter, surveys, community engagement events, etc.). The County can use these existing means to communicate flood and drought risk and response, following the recommended pathways for risk communication outlined in Action V5.3.



Proximity to Astotin Creek and the primary use of private land will impact the relative risk of a residential property to flood and drought and will influence the responsibilities and applicable behaviours of the resident. Communications (outreach events, communications, etc.) may be tailored to different land users and owners, with a focus on personal property protection for those likely to be directly impacted by flood or drought. Targeted outreach events with invitations to directly affected landowners and residents can help to address specific risk communication and actions regarding flood and drought protection, such as property-level flood protection. Targeted events may include stakeholder engagement sessions or targeted mail-outs.

General community awareness of how the County is assessing and addressing flood and drought risk, and what individuals can do to mitigate personal and community risk, will support overall community awareness of flood, drought, and associated climate change-related risk. Establishing a baseline understanding of community awareness of flood and drought, through the surveys completed during this project, will help inform appropriate public outreach activities based on gaps in awareness.

An aware public is better able to understand and support County decisions around flood and drought risk management. Informed landowners are better able to take proactive measures to protect their property from flood and drought and will have an improved understanding of the roles and responsibilities of the County relative to their own. Actively engaged residents can help the County to identify risks and practical and relevant adaptive strategies to manage those risks.

Applicability

Applicable to all County residents, with targeted activities for landowners and residents directly impacted by flood and drought.

Public outreach programs recommended in this plan address all areas of the watershed, and a variety of topics, from ecosystem restoration and function to hydrology and engineering solutions and emergency preparedness. Specific public outreach activities which have been identified throughout the Action Plan are highlighted in the following table.



Table 4-3 Actions with Public Outreach Component

Associated Action(s)	Public Outreach Objectives
V1.1, V1.2, V2.1, & V2.3	Build understanding of the benefits of a vegetated buffer and natural water retention features; provide landowners with information on alternative land use practices to promote healthy riparian area
V1.2 & V2.1	Build understanding of wetland conservation and restoration benefits. Work with interested landowners to identify potential wetland restoration sites.
V1.4	Raise awareness of the presence of wildlife and benefits of co-existence.
V1.5	Build understanding of the benefits of aquatic connectivity and the types of obstructions which pose a risk to creek flow and connectivity.
V1.6	Build understanding of livestock impacts on riparian areas and provide information on livestock management options to reduce impacts.
V4.4	Build understanding of how debris can impact the watershed and promote ongoing debris management practices.
V5.4	Build public understanding of flood and drought risks, flood prevention measures, property protection measures, and emergency response.

Cost

Various grant programs are available to support public outreach activities and could support County staffing and additional resources for program delivery, with or in cooperation with relevant non-governmental organizations (e.g., Cows and Fish, ALUS).

There is little to no capital cost to establishing a public outreach campaign, but staff time and resources will be required.





V 6.2

IMPLEMENT PILOT PROGRAMS TO SHOWCASE NATURE-BASED SOLUTIONS

Description of Action

For many members of the public, engineering solutions are a broadly recognized, traditional solution to flooding concerns. However, in the context of limitations to government funding, climate change, and a need for adaptation to flood and drought risk, nature-based solutions are of increasing interest. Residents and other stakeholders may not be familiar with such solutions, or the expectations of community involvement in their application, and introducing several changes at once may be overwhelming. Pilot projects conducted with willing landowners can provide ‘proof of concept’ as well as local champions that can explain the benefits and observed outcomes of the project. For this reason, choice of project is also critical: building up from a series of achievable projects with less risk of failure will foster more trust. Potential pilot projects that could be implemented with interested landowners include the following:

- Restoration of a section of riparian flood fringe or wetland area (e.g., by eliminating mowing, or by planting native species in previously cultivated areas).
- Installation of an off-stream livestock watering station and fencing a section of riparian pasture to regulate livestock access to the creek.
- Installation of beaver pond levelers to manage pond extent (e.g., in the Upper or Lower Assessment Reach).

Each pilot project would require some level of monitoring, ideally involving the participating landowner, or other interested groups (e.g., school classes, 4H clubs), and creating realistic expectations of the period for observing positive effects. Monitoring results can be reported back to the community through County communications, or through media coverage to share the results, generate community interest, and ultimately promote adoption of resiliency strategies.



Benefits

Pilot projects with high probability of success can demonstrate tangible positive results resulting from changes in practice. Early success with such initiatives is key to building community trust and maintaining the support of the sponsoring landowner.

Applicability

Pilot projects could be developed anywhere in the watershed, but to have maximum effect, should reflect the priorities for action, and if possible, an area best representing the management concern.

Cost

Pilot project costs will vary based on their complexity. A beaver pond leveler installation can range from \$1000 to \$2000 for materials, while an ecological restoration project using native plant seeds or seedling could be more expensive, depending on planting requirements and plant availability. A variety of funding programs provide support for such projects (e.g., Green Acreages, provincial watershed protection grants), and could be secured by the County or the landowner (e.g., for an industry partner).



V 6.3

IMPLEMENT CITIZEN SCIENCE INITIATIVES

Description of Action

Public engagement can be encouraged through outreach, but also through active participation in some part of flood and drought management. Various examples of potential citizen science programs have been suggested for the visions in previous sections. The launch of the iNaturalist and NatureLynx Astotin projects as part of the State of the Watershed assessment has started this process, by encouraging citizen scientists and residents to record their observations during their home, work, and recreational activities. Future initiatives could include community-based monitoring of debris in the mainstem



creek and tributaries or encouraging reporting observations of ‘nuisance’ wildlife encounters. Other examples that could help raise awareness of creek hydrology and flood risk among local residents could include volunteer monitoring of stream gauges at set locations along the creek, or even reporting local rainfall events to the County.

Some initial costs include supplies (e.g., free rain gauges offered to landowners, or installation of simple stream gauges at strategic locations on private lands) and training. Data management and quality controls will also be important, to provide checks of the accuracy of reporting by residents. For example, County monitored stream gauges can be used to confirm readings from residents, and rainfall recordings from Environment Canada monitoring stations in Elk Island National Park provide a reference against residents’ data.

Benefits

Public participation in data collection programs is of increasing interest because it involves stakeholders more directly in the management process. Participants have the satisfaction of contributing to the solution, but also, a better understanding of the constraints and challenges involved in management.

Applicability

Citizen science programs could be implemented anywhere in the watershed, and could be targeted to specific audiences (e.g., agricultural landowners, industrial land managers), or to a broad public audience. There may be an opportunity to partner with organizations such as the Beaver Hills Biosphere or Friends of Elk Island Society to implement citizen science programs.

Cost

The cost of many citizen science projects can be quite low, involving a means of recording or reporting observations, and training in proper technique.



People Power – Citizen Science as an Outreach Tool



Citizen science brings volunteers and scientists together to gather data to answer environmental problems. Often, these projects also build shared understandings of change, risk and need for action.

Examples include outreach that engages volunteers to record plants and animals, like the iNaturalist program used in this study. Other examples include collecting rainfall data, observing spring flowering timing, or annual surveys for specific species, like owls and amphibians. Such studies can raise awareness of issues and help motivate support and, more importantly, action.



V 6.4 INDIGENOUS RELATIONS

Description of Action

Indigenous peoples have inhabited the Astotin Creek watershed and surrounding areas for over 10,000 years and today, First Nation and Metis peoples continue to have a strong connection to the land (MacDonald, 2009; Matters and Hood, 2016). Exploring these connections with Indigenous peoples can help foster a greater understanding of the ecological and land use history in the region and help to build a shared understanding of the watershed. Pilot projects, co-developed with interested Indigenous groups can be used to explore these connections and demonstrate a path forward. Indigenous groups who participated in the engagement program all identified an interest in building stronger relationships with the County and participating in future activities in the Astotin Creek area. The County is committed to continuing to foster these relationships during the implementation of the Resiliency Action Plan.



The Beaver Hills Biosphere is undertaking projects that explore Indigenous history and connection to the land, and the County can potentially collaborate on these initiatives or contribute to the learning network and overall objectives.

Benefits

Collaborating with Indigenous communities will help move the County towards a path of reconciliation and will help build better relationships with Indigenous peoples with connection to this land. Additionally, the County will have more information to help inform decision-making.

Applicability

Indigenous Relations may be incorporated into a number of actions, particularly those related to nature-based solutions. Broader engagement and collaboration with Indigenous groups would be undertaken by relevant County staff and learnings can be shared widely where appropriate. Although programs or projects that require individual landowner collaboration will apply directly to landowners, Indigenous Relations may provide additional perspectives to these initiatives which could enhance learning for County residents and staff.

Cost

Costs of programs, projects, and collaborations will vary but seeking funding partnerships with Indigenous communities can help offset capital costs.



The Treaty Land Sharing Network fosters communication between landowners and Indigenous land users in Treaty 4 and Treaty 6 Territories. Volunteer landowners in the network receive signs to indicate that their lands are open for Indigenous peoples to access for traditional activities and for exercising treaty rights. (Treaty Land Sharing Network, n.d.)





IMPLEMENTATION

5



To support the implementation of recommended actions, the following sections discuss **action prioritization, implementation considerations, and funding opportunities.**

5.1 Action Prioritization

5.1.1 Action Prioritization Methodology

The following criteria have been considered in the action prioritization process:

- Contribution to flood/drought risk reduction
- Environmental benefits
- Economic benefits
- Social benefits
- Capital costs
- Non-capital costs
- Funding availability/alignment & available resources
- Ease of implementation
- County autonomy for implementation
- Low-carbon resilience.

Each criterion was assigned a weighting from 1 – 3 according to input from stakeholders as well as input from Strathcona County staff. Weighting reflects alignment with the County’s strategic priorities and interests of residents and other stakeholders, as communicated in the stakeholder engagement surveys. A scale from 0-3 was used to score each action, as shown in Table 5-1. Criteria evaluation was based on an order of magnitude assessment (i.e. low, moderate, high). This approach was taken as many of the actions are at a conceptual level. A more detailed assessment of benefits, costs, and risks should be undertaken as



actions are further developed in the implementation stage. Prioritization criteria may also need to be revisited if strategic priorities shift. Community needs may change over time, and stakeholder feedback could influence priorities in the future.

In order to prioritize actions, an overall score was calculated for each action. The methodology to calculate scores was to develop a score for each criterion by multiplying the weighting (1-3) and score (0-3) for each criterion. The sum of all criteria scores for each action resulted in a total score for prioritization. Priority rankings within each vision are included in Table 5-2. These rankings indicate action scoring from highest to lowest within each vision. In addition, overall priority levels were assigned based on set thresholds for scores ranging from very low to very high priority. The overall priority scores indicate how the priority of each action compares to all other actions. Overall priority levels for all actions are also included in Table 5 2.

Table 5-1 Prioritization Criteria

Criteria	Weighting	0	1	2	3
Contribution to flood/drought risk reduction	3	No impact on flood/drought risk	Minor risk reduction	Moderate risk reduction	Considerable risk reduction/elimination of risk
Environmental benefits	3	Does not provide environmental benefits	Provides noticeable short-term or localized benefit	Provides short to moderate term benefits	Provides long-term, wide-spread benefit
Economic benefits	2	Does not provide economic benefits	Provides noticeable short-term or localized benefit	Provides short to moderate term benefits	Provides significant and /or long-term benefits
Social benefits	2	Does not provide social benefits	Provides noticeable short-term or localized benefit	Provides short to moderate term benefits	Provides significant and /or long-term benefits
Capital cost	1	High capital cost (>1M)	Moderate capital cost (75K - 1M)	Low capital cost (<75K)	Minimal capital cost (<10K)
Non-capital costs	1	Significant increase to non-capital costs	Moderate increase to non-capital costs	Low increase to non-capital costs	Reduction in overall non-capital costs

Criteria	Weighting	0	1	2	3
Funding alignment & available resources	2	No alignment with available funding and/or available resources	Could apply for funding in partnership	Portion of work eligible for funding and/or can be covered by available resources	Alignment with existing funding program and/or available resources
Ease of Implementation (constructability/regulatory approval/community support)	1	High risk/uncertainty with implementation	Moderate risk/uncertainty with implementation	Low risk/uncertainty with implementation	Minimal risk/uncertainty with implementation
Autonomy	1	No portion of action could be implemented without stakeholder partnership/	High level of stakeholder partnership/collaboration	Some stakeholder partnership/collaboration	County in full control of action
Low-carbon resilience	1	GHG intensive option	Low/Moderate GHG emissions	Minimal or no GHG emissions	Action provides a carbon sink

5.1.2 Action Prioritization Results

The following table includes the results of the action prioritization. As described in the previous section, action prioritization is presented both as a ranking of actions within each vision as well as an overall priority level. The full prioritization matrix is included in Appendix B.

Table 5 -2 Action Priority Level

Vision	Supporting Actions	Priority Ranking Within Vision	Overall Priority Level
Vision 1: Healthy Ecosystem	V1.1 Conserve/restore vegetated buffer	4	Medium
	V1.2 Conserve/restore natural water retention features	3	High
	V1.3 Implement erosion and sediment control measures	5	Low
	V1.4 Implement co-existence with wildlife strategies	1	Very High
	V1.5 Ensure aquatic connectivity	2	High
	V1.6 Prevent livestock from accessing creek	6	Low
Vision 2: Integrated Watershed Management	V2.1 Conserve and restore wetlands	3	High
	V2.2 Develop land buyback and/or compensation programs	2	High
	V2.3 Maintain ecological function in Upper Assessment Reach	1	Very High
	V2.4 Protect and enhance drainage ways	4	Medium
Vision 3: Resilient Infrastructure	V3.1 Replace undersized infrastructure	3	High
	V3.2 Elevate roads along with crossing upgrades	5	Low
	V3.3 Update the allowable stormwater discharge rate for new developments	4	Medium
	V3.4 Incorporate flood construction level requirements in the LUB	2	Very High
	V3.5 Include climate change considerations in infrastructure and development standards/policy	1	Very High
Vision 4: Proactive Management	V4.1 Implement a debris management program	2	Medium
	V4.2 Expand asset management program	3	Medium
	V4.3 Proactive creek inspections and monitoring	4	Low
	V4.4 Landowner education and partnership for private property clean up	1	Medium

Vision	Supporting Actions	Priority Ranking Within Vision	Overall Priority Level
Vision 5: Flood and Drought Preparedness	V5.1 Develop flood response plan and training	3	Low
	V5.2 Develop flood forecast, monitoring, and warning system	3	Low
	V5.3 Develop a drought mitigation plan	2	Medium
	V5.4 Increase public understanding of flood prevention and drought mitigation, property protection and emergency response	2	Medium
	V5.5 Incentivize property level flood protection	1	High
	V5.6 Investigate availability of flood insurance for landowners	4	Very Low
Vision 6: Educated, Engaged, and Empowered Public	V6.1 Implement public outreach programs	3	Low
	V6.2 Implement pilot programs to showcase nature-based solutions	1	Medium
	V6.3 Implement citizen science initiatives	3	Low
	V6.4 Indigenous relations	2	Medium

5.2 Implementation Considerations

Priority levels presented in the previous section are intended to inform action implementation and sequencing. However, it is important to note that when implementing the Resiliency Action Plan, actions from all six visions should be pursued and priority levels within each vision should be considered in conjunction with overall priority level. For example, although the actions within Vision 6: Educated, Engaged, and Empowered Public rated as low and medium priority overall, actions within this vision are crucial as they enable actions within the other visions. The lower ratings for these actions is attributed to the fact that they do not directly correlate to risk reduction or the realization of benefits. However, without stakeholder support, there may be risks to public acceptability for the implementation of other actions, especially those that require collaboration and partnership with stakeholders.

The time required for implementation should also be a consideration for action planning and implementation. The majority of recommended actions require ongoing investment and/or require annual, reoccurring actions. Project based actions may be completed over multiple years due to budget availability. Policy and planning based actions typically require an up-front investment of time and resources, with some follow up action related to enforcement, education, and review/revisions. The following table presents timelines considerations for all actions.

Table 5 -3 Timeline Considerations

Vision	Supporting Actions	Timeline Considerations
Vision 1: Healthy Ecosystem	V1.1 Conserve/restore vegetated buffer	Projects can be prioritized based on risk level and opportunity, and completed over multiple years
	V1.2 Conserve/restore natural water retention features	Projects can be prioritized based on risk level and opportunity, and completed over multiple years
	V1.3 Implement erosion and sediment control measures	Projects can be prioritized based on risk level, and completed over multiple years
	V1.4 Implement co-existence with wildlife strategies	Ongoing, likely requiring annual action
	V1.5 Ensure aquatic connectivity	Projects can be prioritized based on risk level and completed over multiple years. Should be a consideration with the implementation of Action V3.1
	V1.6 Prevent livestock from accessing creek	Ongoing, likely requiring annual action
Vision 2: Integrated Watershed Management	V2.1 Conserve and restore wetlands	Ongoing action
	V2.2 Develop land buyback and/or compensation programs	Ongoing action required to manage program
	V2.3 Maintain ecological function in Upper Assessment Reach	Ongoing action
	V2.4 Protect and enhance drainage ways	Ongoing action

Vision	Supporting Actions	Timeline Considerations
Vision 3: Resilient Infrastructure	V3.1 Replace undersized infrastructure	Projects can be prioritized based on risk level, and completed over multiple years
	V3.2 Elevate roads along with crossing upgrades	Projects can be prioritized based on risk level, and completed over multiple years
	V3.3 Update the allowable stormwater discharge rate for new developments	Short-term action, with some follow-up actions required (i.e. enforcement, education, review/revisions)
	V3.4 Incorporate flood construction level requirements in the LUB	Short-term action, with some follow-up actions required (i.e. enforcement, education, review/revisions)
	V3.5 Include climate change considerations in infrastructure and development standards/policy	Short-term action, with some follow-up actions required (i.e. enforcement, education, review/revisions)
Vision 4: Proactive Management	V4.1 Implement a debris management program	Annual action
	V4.2 Expand asset management program	Initial investment in program development, with ongoing action required
	V4.3 Proactive creek inspections and monitoring	Annual action
	V4.4 Landowner education and partnership for private property clean up	Ongoing/annual
Vision 5: Flood and Drought Preparedness	V5.1 Develop flood response plan and training	Initial investment in plan development, with ongoing action required for training and plan review/revision
	V5.2 Develop flood forecast, monitoring, and warning system	Initial investment in program development, with ongoing action required
	V5.3 Develop a drought mitigation plan	Initial investment in plan development, with ongoing action required for plan review/revision
	V5.4 Increase public understanding of flood prevention and drought mitigation, property protection and emergency response	Ongoing action
	V5.5 Incentivize property level flood protection	Ongoing action, depends on scope/duration of incentive program
	V5.6 Investigate availability of flood insurance for landowners	Short-term action, outreach with landowners may be ongoing
Vision 6: Educated, Engaged, and Empowered Public	V6.1 Implement public outreach programs	Ongoing action
	V6.2 Implement pilot programs to showcase nature-based solutions	Timeline depends on scope of pilot programs
	V6.3 Implement citizen science initiatives	Timeline depends on scope of citizen science initiatives
	V6.4 Indigenous relations	Ongoing action

5.3 Funding Opportunities

There are several current funding opportunities that are aligned with recommended actions. A list of current funding opportunities is provided below for reference, however, funding programs and funding availability will continue to change. This list is provided as a starting point, but further investigation related to applicability will be required to align funding with specific actions. There are some programs in the following list which are not currently accepting applications, however, these have been included so they can be monitored to determine if additional funding may be made available under these programs in the future.

5.3.1 Federal Funding Programs

2 Billion Trees Program

Natural Resources Canada

The 2 Billions Trees Program is a part of the Nature Smart Climate Solutions Fund which is focused on planting trees to capture carbon, enhance biodiversity, and support human well-being.

Eligible participants: Provinces, territories, Indigenous organizations, third party organization (for and not-for profit)

Available funding: \$3.19 billion, over ten years

Application information: Current round of funding deadline is February 2022, however intention is for ongoing application process, more details on Call for Proposal process to be made available in April 2022

Potential alignment: Vision 1: Healthy Ecosystem

Canadian Community-Building Fund

Infrastructure Canada

The Canadian Community-Building Fund supports projects including public transit, wastewater infrastructure, drinking water, solid waste management, community energy systems, local roads and bridges, capacity-building, highways,



local and regional airports, short-line rail, short-sea shipping, disaster mitigation, broadband and connectivity, brownfield redevelopment, culture, tourism, sport, recreation, and fire halls.

Eligible participants: Provinces and territories. Provinces and territories can flow this funding to municipalities.

Available funding: \$255 - \$266 Million per year to be allocated among communities in Alberta

Application information: Applications online through GTF Online system

Potential alignment: Vision 1: Healthy Ecosystem & Vision 3: Resilient Infrastructure

Disaster Mitigation and Adaptation Fund

Infrastructure Canada

The Disaster Mitigation and Adaptation Fund is a merit-based contribution program intended to support public infrastructure projects designed to mitigate current and future climate-related risk and disasters triggered by climate change. Eligible projects include new construction of public infrastructure and/or modification or reinforcement of existing public infrastructure. This can include natural infrastructure that prevents, mitigates, or protects against the impacts of climate change, disasters triggered by natural hazards, and extreme weather.

Eligible participants: Provinces, territories, municipalities, regional government, public sector bodies established or under provincial or territorial statutes, a Canadian public or not-for-profit institution (working with one of the aforementioned bodies), and eligible Indigenous applicants.

Available funding: \$1 Million to \$20 Million for small scale projects, and \$20 Million + for large scale projects, maximum federal contribution is 40% for municipalities

Application information: Next application deadline is July 2022

Potential alignment: Vision 3: Resilient Infrastructure



Eco Action Community Funding Program

Environment and Climate Change Canada

The Eco Action Community Funding program is targeted at programs which have positive environmental outcomes. The current (2022/2023) funding priority is freshwater and is focused on projects which contribute to the improvement of the quality of freshwater through the diversion and reduction of harmful substances and/or restore and protect freshwater ecosystem health.

Eligible participants: Non-profit and non-government organizations (environmental groups, community groups, youth and senior groups, community-based associations, service clubs, and Indigenous organizations). Government groups are eligible to apply if they are partners with a non-profit or non-governmental group.

Available funding: \$25,000 - \$100,000 per project, 50% of total project value must come from sources other than Government of Canada

Application information: Applications for 2022-23 are closed

Potential alignment: Vision 1: Healthy Ecosystem

Environmental Damages Fund

Environment and Climate Change Canada

The Environmental Damages Fund directs funds from fines, court order, and voluntary payments to environmental restoration and conservation projects within Canada. Projects are selected based on the following priorities: restoration, environmental quality improvement, research and development, and education and awareness.

Eligible participants: non-governmental organizations, universities and academic institutions, Indigenous organizations, provincial, territorial and municipal governments

Available funding: Variable

Application information: applications accepted via Grants and Contributions Enterprise Management System (GCEMS)



Potential alignment: Vision 1: Healthy Ecosystem & Vision 6: Education, Engaged, and Empowered Public

National Disaster Mitigation Program

Public Safety Canada

The National Disaster Mitigation Program offers funding for flood mapping, mitigation planning, risk assessments, and investments in non-structural and small-scale structural mitigation projects with a focus on reducing significant and reoccurring flood risk.

Eligible participants: Provincial and territorial governments. Provincial and territorial governments may collaborate with and redistribute funding to eligible entities such as municipal or other local governments, public sector bodies, private sector bodies, Indigenous band councils, international non-government organizations or any combination of these entities.

Available funding: \$20,000,000 available for the 2021-2022 fiscal year. Funding amounts vary annually based on federal budget.

Application information: Availability of additional funding for future fiscal years has not yet been communicated.

Potential alignment: Vision 3: Resilient Infrastructure

Nature Smart Climate Solutions

Environmental and Climate Change Canada (ECCC)

The portion of the Nature Smart Climate Solutions Fund administered by ECCC is a ten-year fund focused on reducing greenhouse gas emissions using natural climate solutions which also support human well-being and biodiversity. This fund is intended to support projects which focus on conserving, restoring, and enhancing wetlands, peatlands and grasslands to store and capture carbon. The 2021 application process included three streams:

- place-based actions stream (focused on restoration projects and enhanced land management activities and/or projects that prevent GHG emissions from degradation/loss of carbon-rich habitat);



- sector-based policy stream (focused on advancing policies, programs, and tools to support nature-based solutions); and
- reverse auction pilot stream (piloting a reverse auction for agricultural land to reduce GHG emissions or increase carbon sequestration)

Eligible participants: Provinces, territories, Indigenous organizations, governments and groups, municipal and local governments, not-for-profit organizations, academic institutions, Canadian individuals, domestic or international for-profit organizations, local organizations.

Available funding: \$631 Million, over ten years

Application information: Applications for the 2021 program were due in January 2022, details on subsequent applications have not yet been released

Potential alignment:

- Place-based actions stream: Vision 1: Healthy Ecosystem
- Sector-based policy stream: Vision 2: Integrated Watershed Management
- Reverse auction pilot stream: Vision 2: Integrated Watershed Management

5.3.2 Provincial Funding Programs

Alberta Community Resilience Program

Government of Alberta

The Alberta Community Resilience Program (ACRP) is a multi-year grant program supporting the development of long-term resilience to flood and drought events, while supporting integrated planning and healthy, functioning watersheds. The ACRP provides grants for the design and construction of projects that protect critical infrastructure from flooding and drought and help to ensure public safety is protected.

Eligible participants: Municipalities, First Nations, Metis settlements, improvement districts, and special areas

Available funding: 90% of funding for eligible engineering and construction costs up to \$3 Million and 70% of costs in excess of \$3 Million

Application information: Program is no longer accepting applications.

Potential alignment: Vision 2: Integrated Watershed Management & Vision 3: Resilient Infrastructure

Investing in Canada Infrastructure Program-Green Infrastructure Stream
Infrastructure Canada and Government of Alberta

The green infrastructure stream supports green infrastructure projects with outcomes across climate change mitigation, adaptation, resilience and disaster mitigation, and environmental quality.

Eligible participants: Provinces, territories, municipalities, not-for profit projects, Indigenous groups, private sector projects.

Available funding: 40% of project costs for municipal groups

Application information: The program is not accepting applicants at this time.

Potential alignment: Vision 1: Healthy Ecosystem

Municipal Stimulus Program
Government of Alberta

Municipal Stimulus Program funding is allocated for projects to sustain and create local jobs, enhance provincial competitiveness and productivity, position communities to participate in future economic growth, and reduce municipal red tape to promote job-creating private sector investment. Municipalities will be required to commit to taking concrete actions to reduce red tape and encourage private sector investment.

Eligible participants: Municipalities and Metis Settlements.

Available funding: \$50,000 minimum funding, \$500 million total available

Application information: Program is now closed to new applications.

Potential alignment: Vision 3: Resilient Infrastructure



Municipal Sustainability Initiative

Government of Alberta

The Municipal Sustainability Initiative funds capital projects including roads, bridges, public transit vehicles or facilities, emergency services facilities or equipment, water and wastewater systems, solid waste management facilities or equipment, regional and community airport facilities or equipment, and other municipal buildings such as recreation and sports facilities, libraries, public works buildings, and cultural and community centres. Operating projects including capacity building activities that improve efficiency or effectiveness, municipal services, planning activities, and assistance to non-profit organizations.

Eligible participants: Municipalities

Available funding: Funding is allocated based on municipal status with \$722 million available per year between 2021 and 2023, funding amounts are allocated to municipalities throughout Alberta

Application information: ongoing applications

Potential alignment: Vision 3: Resilient Infrastructure & Vision 4: Proactive Management

Watercourse Crossing Remediation Grant Program

Alberta Environment and Parks (AEP)

The Watercourse Crossing Remediation Grant Program was created in 2021 to support municipalities in the remediation and reclamation of roadway crossings which are impacting fish habitation through erosion, excessive sedimentation, and/or fragmentation of fish habitat.

Eligible participants: Municipalities

Available funding: \$8.5 million in total, funding granted annually between 2021 and 2024

Application information: This funding is granted annually. 2021 applications were due in October 2021. Details on upcoming application deadlines not yet available.

Potential alignment: Vision 1: Healthy Ecosystem & Vision 3: Resilient Infrastructure



Watershed Resiliency and Restoration Program

Alberta Environment and Parks (AEP)

The Watershed Resiliency and Restoration Program focuses on projects that will advance flood and drought resiliency in priority areas, restore, and enhance ecological connectivity and function in critical areas, and increase knowledge, awareness, and tools that enhance watershed resiliency.

Eligible participants: Municipalities, non-governmental organizations, Indigenous communities, incorporated watershed groups, drainage/irrigation districts, and any other group registered under the provincial Societies Act.

Available funding: funding granted annually

Application information: This funding is granted annually. 2021-22 applications were due in November 2021.

Potential alignment: Vision 1: Healthy Ecosystem

Wetland Replacement Program

Alberta Environment and Parks (AEP)

The Wetland Replacement Program aims to re-establish wetlands in partnership with Albertans by providing resources for collaborative restoration projects across the province. Wetland replacement includes both wetland restoration and wetland construction. Strathcona County is already actively engaged in this program and has been identified as a high priority area for wetland replacement by AEP. Strathcona County has initiated an internal Wetland Replacement Program Committee to identify potential wetland replacement projects.

Eligible participants: Municipalities

Available funding: ongoing funding

Application information: Strathcona County is already engaged in a partnership with AEP to take part in this program. As per Strathcona County's internal processes, projects will be brought to Council for approval prior to submission of proposals to AEP.

Potential alignment: Vision 1: Healthy Ecosystem



5.3.3 Non-government Funding Programs

Alberta Ecotrust Environmental Grant Program

Alberta Ecotrust

Alberta Ecotrust has a grant program to support environmental projects throughout Alberta. This program is currently under review and details on the refreshed program will be released later in 2022.

Eligible participants: Alberta environmental non-government organizations, First Nations

Available funding: Information not yet released

Application information: Application details to be released in Summer 2022

Potential alignment: Vision 1: Healthy Ecosystem & Vision 2: Integrated Watershed Management

Community Conservation Action Program

Wildlife Habitat Canada (WHC)

WHC's Community Conservation Action Program supports small organizations in making conservation achievements within their community through projects that connect Canadians with nature, engage in conservation, or provide educational conservation programming.

Eligible participants: Small Canadian Organizations; research, academic, and educational institutions, Indigenous organizations, local organizations.

Available funding: Maximum request of \$10,000. A 1:1 matching contribution is required; Canadian federal funding cannot be included in matching funds.

Application information: Annual applications, 2022-2023 grant year has closed

Potential alignment: Vision 6: Educated, Engaged, and Empowered Public



Green Municipal Fund

Federation of Canadian Municipalities

The Green Municipal fund focuses on projects that are green initiatives with a preference given to pilot projects prior to main projects.

Eligible participants: Municipalities

Available funding: Funding is separated into regular and high-ranking projects. Regular projects are eligible for low-interest loans of up to \$5 Million and a grant worth up to 15% of the loan. High-ranking projects are eligible for low-interest loans of up to \$10 Million and a grant worth up to 15% of the loan. This program will cover up to 80% of eligible costs.

Application information: Ongoing applications, subject to funding availability

Potential alignment: Vision 1: Healthy Ecosystem & Vision 6: Educated, Engaged, and Empowered Public

Habitat Conservation Stamp Initiative

Wildlife Habitat Canada (WHC)

WHC's Habitat Conservation category of the Habitat Conservation Stamp Initiative supports projects that address the North American Waterfowl Management Plan priorities to increase/maintain waterfowl populations, conserve wetland habitat, and increase engagement in habitat conservation.

Eligible participants: Provincial, territorial, municipal, and local governments, Canadian residents, not-for-profit organizations, for-profit organizations, Indigenous organizations, and local organizations.

Available funding: A 1:1 matching contribution is required; Canadian federal funding cannot be included in matching funds.

Application information: annual applications, 2022-2023 grant year has closed

Potential alignment: Vision 1: Healthy Ecosystem



Municipal Asset Management Program

Federation of Canadian Municipalities

The Municipal Asset Management Program provides Canadian municipalities with funding to conduct asset management assessments, develop asset management plans, policies, and strategies, conduct asset-related data collection and reporting, provide asset management training and organization development, and transfer knowledge around asset management.

Eligible participants: Canadian municipal governments or municipal partners applying in association with a municipal government (municipal owned corporations, region/provincial/territorial governments delivering municipal services, Indigenous communities, and not-for profit organizations that focus on municipal services).

Available funding: 80% of total eligible project costs to a maximum of \$50,000 for individual applications.

Application information: no deadline to apply, but grants are subject to fund availability. Municipalities may apply for a second-time if application includes asset management knowledge sharing component.

Potential alignment: Vision 4: Proactive Management

Watershed Stewardship Grants

Land Stewardship Centre

The Watershed Stewardship Grants are provided to support collaborative, community-based stewardship efforts consistent with the principles, goals, and outcomes of Alberta's Water for Life Strategy.

Eligible participants: Alberta-based, community-oriented, and volunteer-based partnerships that actively engage in environmental stewardship of their watershed. Municipal governments and government agencies are not eligible to apply directly for this grant. They may, however, serve as the partnering legal entity for a group that does not have legal status.

Available funding: \$20,000 per year

Application information: 2022 applications were due February 14, 2022, details for future funding applications not yet available

Potential alignment: Vision 6: Educated, Engaged, and Empowered Public





ACKNOWLEDGMENTS

6



The County would like to acknowledge and share our appreciation for all of the residents, stakeholders, and Indigenous groups who participated in this project.

We are proud to share that the Astotin Creek Resiliency Study was awarded the Consulting Engineers of Alberta 2022 Environmental Award of Excellence. (Appendix C).





REFERENCES

7



Alberta Agriculture and Forestry. (2020). Alberta Soil Information Viewer. Retrieved August 2021 from [https://www1.agric.gov.ab.ca/\\$department/deptdocs.nsf/all/sag10372](https://www1.agric.gov.ab.ca/$department/deptdocs.nsf/all/sag10372).

Alberta Ecotrust. (2022, February 17). Alberta Ecotrust Environmental Grant Program. Retrieved from: <https://albertaecotrust.com/what-we-do/environmental-grants/>

Alberta Environment and Sustainable Resource Development. (2012). Stepping Back from the Water - A Beneficial Management Practices Guide For New Development Near Water Bodies in Alberta's Settled Region. Retrieved from: <https://open.alberta.ca/dataset/1c70eb43-a211-4e9c-82c3-9ffd07f64932/resource/6e524f7c-0c19-4253-a0f6-62a0e2166b04/download/2012-steppingbackfromwater-guide-2012.pdf>

Alberta Transportation. (2006). Hydrotechnical Design Guidelines for Stream Crossings. Retrieved from: <http://www.transportation.alberta.ca/Content/doctype30/Production/HyDgnGLStCr.pdf>

ALUS. (2021, November 29). Environmental Stewardship through Ecosystem Services. Retrieved from: <https://alus.ca/what-we-do/>

Auster, R.E., Barr, S.W. & Brazier, R.E. (2021). Improving engagement in managing reintroduction conflicts: learning from beaver reintroduction. Journal of Environmental Planning and Management, 64:10, 1713-1734, DOI: 10.1080/09640568.2020.1837089

Bush, E. & Lemmen, D.S. (Eds.). (2019). Canada's Changing Climate Report. Government of Canada.

Canfax - Division of the Canadian Cattleman's Association. (2018). Economics of Water Systems. Canadian Cattleman's Association. Retrieved from: www.canfax.ca/research

Cows and Fish. (2021, November 29). About Cows and Fish. Retrieved from: <https://cowsandfish.org/about-us/>

City of Toronto. 2019. Basement flooding protection subsidy program. Basement flooding. <https://www.toronto.ca/services-payments/water-environment/managing-rainmelted-snow/basement-flooding/basement-floodingprotection-subsidy-program/>

Dittbrenner, B.J. (2019). Restoration potential of beaver for hydrological resilience in a changing climate. PhD Thesis. University of Washington.

Federation of Canadian Municipalities. (2021, November 29). Green Municipal Fund. Retrieved from: <https://fcm.ca/en/programs/green-municipal-fund>

Federation of Canadian Municipalities. (2021, November 29). Municipal Asset Management Program. Retrieved from: <https://fcm.ca/en/programs/municipal-asset-management-program>
Government of Alberta. (2021, November, 29). Alberta Community Resilience Program. Retrieved from: <https://www.alberta.ca/alberta-community-resilience-program.aspx>

Government of Alberta. (2021, November, 29). Investing In Canada Infrastructure Program. Retrieved from: <https://www.alberta.ca/investing-canada-infrastructure-program.aspx>

Government of Alberta. (2021, November, 29). Municipal Stimulus Program. Retrieved from: <https://www.alberta.ca/municipal-stimulus-program.aspx>



Government of Alberta. (2021, November, 29). Municipal Sustainability Initiative. Retrieved from: <https://www.alberta.ca/municipal-sustainability-initiative.aspx>
Government of Alberta. (2021). Watercourse Crossing Remediation Grant Program 2021-2024 Application Guide. Retrieved from: <https://open.alberta.ca/dataset/afda3f66-bc18-4d3d-b1f1-2014863d005f/resource/2c58addc-629c-41bb-971f-755e7efaf407/download/aep-watercourse-crossing-remediation-grant-program-application-guide-2021-2024.pdf>

Government of Alberta. (2021, November, 29). Watershed Resiliency and Restoration Program. Retrieved from: <https://www.alberta.ca/watershed-resiliency-and-restoration-program.aspx>

Government of Alberta (2021). Wetland Replacement Program. Retrieved from: <https://open.alberta.ca/dataset/7d5222a6-a62b-4292-b3c3-37863fea6a02/resource/dea4f767-6c6d-462a-ac1d-f88baba3002d/download/aep-wetland-replacement-program-factsheet-2021-11.pdf>

Government of Canada. (2022, February, 17). 2 Billion Trees Commitment. Retrieved from: <https://www.canada.ca/en/campaign/2-billion-trees.html>

Government of Canada. (2021, November, 29). Disaster Mitigation and Adaptation Fund. Retrieved from: <https://www.infrastructure.gc.ca/dmaf-faac/index-eng.html>

Government of Canada. (2021, November, 29). EcoAction Community Funding Program. Retrieved from: <https://www.canada.ca/en/environment-climate-change/services/environmental-funding/ecoaction-community-program.html>

Government of Canada. (2022, February, 18). Environmental Damages Fund. Retrieved from: <https://www.canada.ca/en/environment-climate-change/services/environmental-funding/programs/environmental-damages-fund.html>

Government of Canada. (2021, November, 29). The Canada Community-Building Fund. <https://www.infrastructure.gc.ca/plan/gtf-fte-eng.html>

Government of Canada. (2021, November, 29). Nature Smart Climate Solutions Fund. Retrieved from: <https://www.canada.ca/en/environment-climate-change/services/environmental-funding/programs/nature-smart-climate-solutions-fund.html>

Hessey, K. (2021, October 2). How a river in Quebec won the right to be a legal person. Global News. <https://globalnews.ca/news/8230677/river-quebec-legal-person/>

Insurance Bureau and Canada and Federation of Canadian Municipalities. (2020). Investing in Canada's Future: The Cost of Climate Adaptation at the Local Level.

International Union for Conservation of Nature. (2019). Nature based solutions for societal needs – a standardized approach for design and verification of interventions. Retrieved October 2021 from https://www.iucn.org/sites/dev/files/content/documents/2019/iucn_global_nbs_standard_-_public_consultation.pdf

Fairfax, E. and Whittle, A. (2020), Smokey the Beaver: beaver-dammed riparian corridors stay green during wildfire throughout the western USA. Ecol Appl. Accepted Author Manuscript. doi:10.1002/eap.2225

Land Stewardship Centre. (2021, November, 29). Watershed Stewardship Grants. Retrieved from: <https://www.landstewardship.org/watershed-stewardship-grant-program/>



MacKinnon, J., Heldsinger, N. and S. Peddle. 2018. A Community Guide for Effective Flood Risk Communication. Waterloo, Ontario: Partners for Action.

MacDonald, G.A. (2009). The Beaver Hills Country: A history of land and life. AU Press, Athabasca University.

Matters, S. & Hood, G. (2016). An analysis of the history of Aboriginal peoples in the Beaver Hills, Alberta, Canada. The Canadian Journal of Native Studies, XXXVI (2), 149-166.

Miistakis Institute. (n.d.). Putting Beavers to Work - Project Research and Outcomes. <https://www.rockies.ca/beavers/research.php>

Nelson, S.N. & Paetz, M.J. (1992). The Fishes of Alberta (2nd ed.). The University of Alberta Press.
Proulx, B. (2018). Strathcona County grapples with flooding. Fort Saskatchewan The Record, April 26, 2018. Retrieved September 22, 2021 <https://www.fortsaskatchewanrecord.com/2018/04/26/strathcona-county-grapples-with-flooding>

Public Safety Canada. (2021, November, 29). National Disaster Mitigation Program (NDMP). Retrieved from: <https://www.publicsafety.gc.ca/cnt/mrgnc-mngmnt/dsstr-prvntn-mtgtn/ndmp/index-en.aspx>

Spencer Environmental Management Services Ltd. (2005). Assessment of Environmental Sensitivity and Sustainability in Support of the Strathcona County MDP Review. Prepared for Strathcona County.

Strathcona County. (2015). LUB 6-2015. Strathcona County, AB: Strathcona County.

Strathcona County. (2020). Municipal Development Plan Bylaw 20-2017. Strathcona County, AB: Strathcona County.

Strathcona County. (2021). Environmental Framework. Strathcona County, AB: Strathcona County.
Schwab, J. (Ed.). (2013) Planning and Drought. American Planning Association.

Thistlethwaite, Jason & Henstra, Daniel & Brown, Craig & Scott, Daniel. (2018). How Flood Experience and Risk Perception Influences Protective Actions and Behaviours among Canadian Homeowners. Environmental Management. 61. 1-12. 10.1007/s00267-017-0969-2.

Treaty Land Sharing Network. (n.d.). Access Land. Retrieved from: <https://treatylandsharingnetwork.ca/access-land/>

University of Nebraska National Drought Mitigation Centre. (2021, November 29) Planning for Drought. Retrieved from: <https://drought.unl.edu/Education/DroughtBasics.aspx>

Wildlife Habitat Canada. (2021, November, 29). Community Conservation Action Program. Retrieved from: <https://whc.org/ccap/>

Wildlife Habitat Canada. (2021, November, 29). Habitat Conservation Stamp Initiative. Retrieved from: <https://whc.org/grants/>







UNDERSIZED CROSSINGS

A





Legend

- Station Marker
- Structures
- Undersized Crossings
- Overtopped Roads
- ~ Astotin Creek
- Astotin Watershed
- - - Hydraulic Model Boundaries
- 100 Year Flood Inundation
- Marsh
- Swamp
- Open Water
- Astotin Lake

Notes:

- 1) The flood maps were created using a two-dimensional hydrodynamic HEC-RAS model and a Digital Elevation Model (DEM) of the Astotin Creek Watershed
- 2) The DEM was created by combining the 2018 LiDAR data collected by Airborne Imaging with the bathymetric data collected by WSP in 2021.
- 3) The HEC-RAS model was calibrated for low-flow conditions but no calibration data for high flood events were available, limiting the model's accuracy at high flows.
- 4) The flood maps do not consider blockage of bridges and culverts that may develop during large flood events.
- 5) The flood maps only consider flooding due to Astotin Creek flows and do not include local impoundments due to flooding issues.

Astotin Creek Resiliency Study

Appendix A: 100-Year Flood Inundation Map with Locations of Undersized Crossings and Overtopped Roads



**Astotin Creek
Alberta**

Scale: 1:10,000



Report By: AH WSP Job #: 211-03754-00
Drawn by: JH Date: August 9, 2021
Reviewed By: AH Office: Edmonton

Notes: Data provided by Altalis; Natural Resource Canada; ESRI



Legend

- Station Marker
- Structures
- Undersized Crossings
- Overtopped Roads
- ~ Astotin Creek
- Astotin Watershed
- Hydraulic Model Boundaries
- 100 Year Flood Inundation
- Marsh
- Swamp
- Open Water

Notes:

- 1) The flood maps were created using a two-dimensional hydrodynamic HEC-RAS model and a Digital Elevation Model (DEM) of the Astotin Creek Watershed
- 2) The DEM was created by combining the 2018 LiDAR data collected by Airborne Imaging with the bathymetric data collected by WSP in 2021.
- 3) The HEC-RAS model was calibrated for low-flow conditions but no calibration data for high flood events were available, limiting the model's accuracy at high flows.
- 4) The flood maps do not consider blockage of bridges and culverts that may develop during large flood events.
- 5) The flood maps only consider flooding due to Astotin Creek flows and do not include local impoundments due to flooding issues.

Astotin Creek Resiliency Study

Appendix A: 100-Year Flood Inundation Map with Locations of Undersized Crossings and Overtopped Roads



**Astotin Creek
Alberta**

Scale: 1:10,000



Report By: AH WSP Job #: 211-03754-00
Drawn by: JH Date: August 9, 2021
Reviewed By: AH Office: Edmonton

Notes: Data provided by Altalis; Natural Resource Canada; ESRI



Legend

- Station Marker
- Structures
- Undersized Crossings
- Overtopped Roads
- Astotin Creek
- Astotin Watershed
- Hydraulic Model Boundaries
- 100 Year Flood Inundation
- Marsh
- Swamp
- Open Water

Notes:


- 1) The flood maps were created using a two-dimensional hydrodynamic HEC-RAS model and a Digital Elevation Model (DEM) of the Astotin Creek Watershed
- 2) The DEM was created by combining the 2018 LiDAR data collected by Airborne Imaging with the bathymetric data collected by WSP in 2021.
- 3) The HEC-RAS model was calibrated for low-flow conditions but no calibration data for high flood events were available, limiting the model's accuracy at high flows.
- 4) The flood maps do not consider blockage of bridges and culverts that may develop during large flood events.
- 5) The flood maps only consider flooding due to Astotin Creek flows and do not include local impoundments due to flooding issues.

Astotin Creek Resiliency Study

Appendix A: 100-Year Flood Inundation Map with Locations of Undersized Crossings and Overtopped Roads

Astotin Creek
Alberta

Scale: 1:10,000




Universal Transverse Mercator (Zone 12)
North American Datum (1983)



Report By: AH WSP Job #: 211-03754-00
Drawn by: JH Date: August 9, 2021
Reviewed by: AH Office: Edmonton

Notes: Data provided by Altalis; Natural Resource Canada; ESRI



- Legend**
- Station Marker
 - Structures
 - Undersized Crossings
 - Overtopped Roads
 - ~ Astotin Creek
 - Astotin Watershed
 - - - Hydraulic Model Boundaries
 - 100 Year Flood Inundation
 - Marsh
 - Swamp
 - Open Water

- Notes:**
- 1) The flood maps were created using a two-dimensional hydrodynamic HEC-RAS model and a Digital Elevation Model (DEM) of the Astotin Creek Watershed
 - 2) The DEM was created by combining the 2018 LiDAR data collected by Airborne Imaging with the bathymetric data collected by WSP in 2021.
 - 3) The HEC-RAS model was calibrated for low-flow conditions but no calibration data for high flood events were available, limiting the model's accuracy at high flows.
 - 4) The flood maps do not consider blockage of bridges and culverts that may develop during large flood events.
 - 5) The flood maps only consider flooding due to Astotin Creek flows and do not include local impoundments due to flooding issues.

Astotin Creek Resiliency Study

Appendix A: 100-Year Flood Inundation Map with Locations of Undersized Crossings and Overtopped Roads



**Astotin Creek
Alberta**

Scale: 1:10,000



Report By: AH WSP Job #: 211-03754-00
Drawn by: JH Date: August 9, 2021
Reviewed by: AH Office: Edmonton

Notes: Data provided by Altalis; Natural Resource Canada; ESRI




- Legend**
- Station Marker
 - Structures
 - Undersized Crossings
 - Overtopped Roads
 - ~ Astotin Creek
 - ▭ Astotin Watershed
 - - - Hydraulic Model Boundaries
 - 100 Year Flood Inundation
 - Marsh
 - Swamp
 - Open Water

- Notes:**
- 1) The flood maps were created using a two-dimensional hydrodynamic HEC-RAS model and a Digital Elevation Model (DEM) of the Astotin Creek Watershed
 - 2) The DEM was created by combining the 2018 LiDAR data collected by Airborne Imaging with the bathymetric data collected by WSP in 2021.
 - 3) The HEC-RAS model was calibrated for low-flow conditions but no calibration data for high flood events were available, limiting the model's accuracy at high flows.
 - 4) The flood maps do not consider blockage of bridges and culverts that may develop during large flood events.
 - 5) The flood maps only consider flooding due to Astotin Creek flows and do not include local impoundments due to flooding issues.

Astotin Creek Resiliency Study



Appendix A: 100-Year Flood Inundation Map with Locations of Undersized Crossings and Overtopped Roads

**Astotin Creek
Alberta**



Report By: AH WSP Job #: 211-03754-00
Drawn by: JH Date: August 9, 2021
Reviewed By: AH Office: Edmonton

Notes: Data provided by Altalis; Natural Resource Canada; ESRI



Legend

- Station Marker
- Structures
- Undersized Crossings
- Overtopped Roads
- ~ Astotin Creek
- Astotin Watershed
- Hydraulic Model Boundaries
- 100 Year Flood Inundation
- Marsh
- Swamp
- Open Water

Notes:


- 1) The flood maps were created using a two-dimensional hydrodynamic HEC-RAS model and a Digital Elevation Model (DEM) of the Astotin Creek Watershed
- 2) The DEM was created by combining the 2018 LiDAR data collected by Airborne Imaging with the bathymetric data collected by WSP in 2021.
- 3) The HEC-RAS model was calibrated for low-flow conditions but no calibration data for high flood events were available, limiting the model's accuracy at high flows.
- 4) The flood maps do not consider blockage of bridges and culverts that may develop during large flood events.
- 5) The flood maps only consider flooding due to Astotin Creek flows and do not include local impoundments due to flooding issues.

Astotin Creek Resiliency Study

Appendix A: 100-Year Flood Inundation Map with Locations of Undersized Crossings and Overtopped Roads

**Astotin Creek
Alberta**

Scale: 1:10,000





Universal Transverse Mercator (Zone 12)
North American Datum (1983)



Report By: AH WSP Job #: 211-03754-00
Drawn by: JH Date: August 9, 2021
Reviewed By: AH Office: Edmonton

Notes: Data provided by Altalis; Natural Resource Canada; ESRI



Legend

- Station Marker
- Structures
- Overtopped Roads
- ~ Astotin Creek
- ▭ Astotin Watershed
- - - Hydraulic Model Boundaries
- 100 Year Flood Inundation
- Marsh
- Swamp
- Open Water

Notes:

- 1) The flood maps were created using a two-dimensional hydrodynamic HEC-RAS model and a Digital Elevation Model (DEM) of the Astotin Creek Watershed
- 2) The DEM was created by combining the 2018 LiDAR data collected by Airborne Imaging with the bathymetric data collected by WSP in 2021.
- 3) The HEC-RAS model was calibrated for low-flow conditions but no calibration data for high flood events were available, limiting the model's accuracy at high flows.
- 4) The flood maps do not consider blockage of bridges and culverts that may develop during large flood events.
- 5) The flood maps only consider flooding due to Astotin Creek flows and do not include local impoundments due to flooding issues.

Astotin Creek Resiliency Study

Appendix A: 100-Year Flood Inundation Map with Locations of Undersized Crossings and Overtopped Roads

**Astotin Creek
Alberta**

Scale: 1:10,000



0 50 100 200 300 400 500 Meters

Universal Transverse Mercator (Zone 12)
North American Datum (1983)

wsp

Report By: AH	WSP Job #: 211-03754-00
Drawn by: JH	Date: August 9, 2021
Reviewed By: AH	Office: Edmonton

Notes: Data provided by Altalis; Natural Resource Canada; ESRI



Legend

- Station Marker
- Structures
- Undersized Crossings
- Overtopped Roads
- ~ Astotin Creek
- ▭ Astotin Watershed
- - - Hydraulic Model Boundaries
- 100 Year Flood Inundation
- Marsh
- Swamp
- Open Water

Notes:

- 1) The flood maps were created using a two-dimensional hydrodynamic HEC-RAS model and a Digital Elevation Model (DEM) of the Astotin Creek Watershed
- 2) The DEM was created by combining the 2018 LiDAR data collected by Airborne Imaging with the bathymetric data collected by WSP in 2021.
- 3) The HEC-RAS model was calibrated for low-flow conditions but no calibration data for high flood events were available, limiting the model's accuracy at high flows.
- 4) The flood maps do not consider blockage of bridges and culverts that may develop during large flood events.
- 5) The flood maps only consider flooding due to Astotin Creek flows and do not include local impoundments due to flooding issues.

Astotin Creek Resiliency Study

Appendix A: 100-Year Flood Inundation Map with Locations of Undersized Crossings and Overtopped Roads



Astotin Creek
Alberta

Scale: 1:10,000



Report By: AH WSP Job #: 211-03754-00
Drawn by: JH Date: August 9, 2021
Reviewed By: AH Office: Edmonton

Notes: Data provided by Altalis; Natural Resource Canada; ESRI



Legend

- Station Marker
- Structures
- Undersized Crossings
- Overtopped Roads
- ~ Astotin Creek
- Astotin Watershed
- Hydraulic Model Boundaries
- 100 Year Flood Inundation
- Marsh
- Swamp
- Open Water

Notes:


- 1) The flood maps were created using a two-dimensional hydrodynamic HEC-RAS model and a Digital Elevation Model (DEM) of the Astotin Creek Watershed
- 2) The DEM was created by combining the 2018 LiDAR data collected by Airborne Imaging with the bathymetric data collected by WSP in 2021.
- 3) The HEC-RAS model was calibrated for low-flow conditions but no calibration data for high flood events were available, limiting the model's accuracy at high flows.
- 4) The flood maps do not consider blockage of bridges and culverts that may develop during large flood events.
- 5) The flood maps only consider flooding due to Astotin Creek flows and do not include local impoundments due to flooding issues.

Astotin Creek Resiliency Study

Appendix A: 100-Year Flood Inundation Map with Locations of Undersized Crossings and Overtopped Roads

**Astotin Creek
Alberta**

Scale: 1:10,000





Universal Transverse Mercator (Zone 12)
North American Datum (1983)



Report By: AH WSP Job #: 211-03754-00
Drawn by: JH Date: August 9, 2021
Reviewed By: AH Office: Edmonton

Notes: Data provided by Altalis; Natural Resource Canada; ESRI



Legend


- Station Marker
- Structures
- ▭ Undersized Crossings
- Overtopped Roads
- ~ Astotin Creek
- ▭ Astotin Watershed
- - - Hydraulic Model Boundaries
- 100 Year Flood Inundation
- Marsh
- Swamp
- Open Water

- Notes:
- 1) The flood maps were created using a two-dimensional hydrodynamic HEC-RAS model and a Digital Elevation Model (DEM) of the Astotin Creek Watershed
 - 2) The DEM was created by combining the 2018 LiDAR data collected by Airborne Imaging with the bathymetric data collected by WSP in 2021.
 - 3) The HEC-RAS model was calibrated for low-flow conditions but no calibration data for high flood events were available, limiting the model's accuracy at high flows.
 - 4) The flood maps do not consider blockage of bridges and culverts that may develop during large flood events.
 - 5) The flood maps only consider flooding due to Astotin Creek flows and do not include local impoundments due to flooding issues.



Astotin Creek Resiliency Study

Appendix A: 100-Year Flood Inundation Map with Locations of Undersized Crossings and Overtopped Roads

Astotin Creek
Alberta



Notes: Data provided by Altalis; Natural Resource Canada; ESRI



Legend

- Station Marker
- Structures
- Overtopped Roads
- Astotin Creek
- ▭ Astotin Watershed
- - - Hydraulic Model Boundaries
- 100 Year Flood Inundation
- Marsh
- Swamp
- Open Water

Notes:

- 1) The flood maps were created using a two-dimensional hydrodynamic HEC-RAS model and a Digital Elevation Model (DEM) of the Astotin Creek Watershed
- 2) The DEM was created by combining the 2018 LiDAR data collected by Airborne Imaging with the bathymetric data collected by WSP in 2021.
- 3) The HEC-RAS model was calibrated for low-flow conditions but no calibration data for high flood events were available, limiting the model's accuracy at high flows.
- 4) The flood maps do not consider blockage of bridges and culverts that may develop during large flood events.
- 5) The flood maps only consider flooding due to Astotin Creek flows and do not include local impoundments due to flooding issues.

Astotin Creek Resiliency Study

Appendix A: 100-Year Flood Inundation Map with Locations of Undersized Crossings and Overtopped Roads

**Astotin Creek
Alberta**

Scale: 1:10,000



Report By: AH WSP Job #: 211-03754-00
Drawn by: JH Date: August 9, 2021
Reviewed By: AH Office: Edmonton

Notes: Data provided by Altalis; Natural Resource Canada; ESRI



ACTION PRIORITIZATION MATRIX

B



Vision	Actions	Prioritization Criteria																												Action Prioritization														
		Contribution to flood/drought risk reduction				Environmental benefits				Economic benefits				Social benefits				Capital cost				Non-capital costs				Funding alignment & available resources				Ease of Implementation				Autonomy				Low-carbon resilience				Overall Priority Score	Priority ranking within vision	Overall Priority Level Based on Overall Priority Scores: Very Low: <25 Low: 25 - 29 Medium: 30-35 High: 36 - 40 Very High: >40
		Criteria Weight: 3		3	Criteria Weight: 3		3	Criteria Weight: 2		2	Criteria Weight: 2		2	Criteria Weight: 1		1	Criteria Weight: 1		1	Criteria Weight: 2		2	Criteria Weight: 1		1	Criteria Weight: 1		1	Criteria Weight: 1		1													
		Score	Rationale	Weighted Score	Score	Rationale	Weighted Score	Score	Rationale	Weighted Score	Score	Rationale	Weighted Score	Score	Rationale	Weighted Score	Score	Rationale	Weighted Score	Score	Rationale	Weighted Score	Score	Rationale	Weighted Score	Score	Rationale	Weighted Score	Score	Rationale	Weighted Score													
Vision 1: Healthy Ecosystem	V1.1 Conserve/restore vegetated buffer	2	Reduces evapotranspiration	6	3	Water quality protection, habitat/biodiversity enhancement	9	1	Prevents bank erosion and water quality issues, reducing need for other mitigation measures (i.e. erosion control measures)	2	2	Aesthetic improvements, increased amenity value to property	4	2	Revegetation costs	2	2	Can be supported through existing County programs / staff	2	2	Existing County programs, but also other funding options	4	1	Increasing / replacing missing buffers may be challenging in ag lands	1	2	Will require landowner support	2	3	Revegetation results in carbon sink	3	35	4	Medium										
	V1.2 Conserve/restore natural water retention features	3	Adds to water storage & attenuates flood	9	2	Natural water retention features aid in local water cycles	6	2	Adds to water storage and attenuates flood, reducing risk of flood damage and associated costs	4	2	Aesthetic improvements, increased amenity value to property, reduced risk of damage to property	4	2	Moderate to low capital cost for restoration projects, however depends on scale of project	2	2	Long-term reduction in flood risk is a benefit (may lead to reduced non-capital costs), short-term cost for programming support	2	2	Can be through Wetland Replacement Program, or other grants	4	1	Will require willing landowners	1	1	Will require willing landowners	1	3	Wetland storage sites result in carbon sink	3	36	3	High										
	V1.3 Implement erosion and sediment control measures	1	Reduces the risk of culvert blockage	3	3	Bank protection reduces risk of erosion/sediment release	9	1	Reduces downstream sediment risk and localized bank erosion	2	2	Aesthetic improvements, increased amenity value to property	4	2	Low capital cost for each location	2	2	Can be supported through existing County programs / staff	2	1	Can be through environmental grants	2	1	Will require willing landowners	1	1	Will require willing landowners	1	3	Revegetation/ stable banks result in carbon sink	3	29	5	Low										
	V1.4 Implement co-existence with wildlife strategies	3	Beaver dams can attenuate floods, hold water in drought	9	3	Beaver pond biodiversity and habitat adds to regional biodiversity/ eco-function	9	2	Water availability and biodiversity (pollinators) can provide economic benefits	4	2	Aesthetic improvements, reduced risk of damage to property	4	3	No costs for retention of beaver ponds	3	2	Reduction in non-capital costs	2	2	Potential for grant funding & partnerships for resources	4	1	Beavers are divisive, with split support. Need landowner cooperation	1	2	Need landowner cooperation	2	3	Maintaining beaver ponds provides a carbon sink in pond soils and vegetation	3	41	1	Very High										
	V1.5 Ensure aquatic connectivity	2	Co-benefits of better flow resulting in flood risk reduction	6	3	Improved connection improves habitat	9	2	Co-benefit of better flow contributing to flood risk reduction, reduced risk of damage from flooding	4	2	Improved flow reduces risk of damage to property	4	2	Individual culvert replacements are moderate to low cost, and included in County programs	2	2	For culvert replacements, assuming O&M already integrated into budget	2	2	Potential for grant funding & partnerships for resources	4	3	Full landowner support likely	3	3	Fits with County transportation O&M program	3	1	Low/moderate GHG emissions	1	38	2	High										
	V1.6 Prevent livestock from accessing creek	0	Improvements limited to water quality	0	3	Results in reduced nutrient load/sediment release	9	1	Replacement water access and fencing costs involved, but better riparian management can help sustain water flow	2	1	Creek water quality (and quantity) can improve with restricted access, connection between environmental and community/social well-being	2	3	Fencing, alternative watering equipment costs	3	2	Uptake could be aided by County outreach support, leading to a low non-capital cost	2	2	Potential for grant funding & partnerships for resources	4	1	Will require willing landowners	1	1	Will require willing landowners	1	2	Improved riparian edge can store more carbon in vegetation	2	26	6	Low										
Vision 2: Integrated watershed management	V2.1 Conserve and restore wetlands	3	Adds to water storage & attenuates flood	9	3	Water quality protection, habitat/biodiversity enhancement	9	1	Prevents bank erosion and water quality issues, leading to cost savings (i.e. reduced need for erosion control measures)	2	2	Aesthetic improvements, increased amenity value to property	4	2	Low capital cost for restoration projects, however depends on scale of project	2	2	Long-term reduction in flood risk is a benefit (may lead to reduced non-capital costs), short-term cost for programming support, existing program	2	2	Potential funding with watershed protection grants	4	1	Will require willing landowners	1	1	Will require willing landowners	1	3	Wetland storage sites results in carbon sink	3	37	3	High										
	V2.2 Develop land buyback and/or compensation programs	3	Remove assets at risk from the floodplain	9	3	Land buybacks can be restored to enhance biodiversity	9	2	Reduces property damage overtime, however, may require a larger initial investment. Economic benefits for landowners from compensation (localized benefit)	4	3	Flood risk reduction, compensation provides secured revenue to farmers during large flood events, reduces stress of flood events for landowners	6	1	Land buy-back can be extensive, depending on the area. Compensation would be significantly lower cost	1	1	Minor increase in non-capital cost. Would require internal capacity building and possibly new staff	1	2	Potential funding	4	1	Significant risk with implementation if land owners are not on board	1	1	Fully dependent on stakeholder partnership, County would still need to be involved	1	3	Carbon sink if the lands are reclaimed.	3	39	2	High										
	V2.3 Maintain ecological function in Upper Assessment Reach	3	Retained wide riparian buffer reduces run-off speed, aids in flood attenuation	9	3	Reduced speed of run-off, reduces sediment and contaminant introduction, aids bank stability	9	3	Retained wide riparian buffer reduces run-off speed, aids in flood attenuation and reduces risk of flood damage and associated costs	6	2	Aesthetic improvements, increased amenity value to property	4	3	No capital cost	3	3	Low non-capital cost, enforcement of policy required, flood mapping will enhance existing policy	3	3	Aligned with existing land use policy	6	3	Some landowner challenge with development limitation possible	3	3	Building landowner support would aid in compliance	3	3	Retaining riparian buffer provides a carbon sink	3	49	1	Very High										
	V2.4 Protect and enhance drainage ways	2	Small drainage ways can collect flows / moderate overland flows	6	3	Reduced speed of run-off, reduces sediment and contaminant introduction, aids bank stability. Could increase water storage.	9	2	Retaining existing drainage ways helps reduce flood intensity, but also retains localized soil moisture, benefiting agricultural land use and reducing risk of flood costs	4	1	Aesthetic improvements possible	2	3	Range of costs: lower cost for drainage enhancement to no cost for conservation/protection	3	2	Low non capital cost, enforcement of policy required and/or support for enhancement projects	2	2	Potential funding with watershed protection grants & partnership opportunities	4	1	Significant risk - large shift in land mgmt. practice	1	1	Fully dependent on landowner cooperation	1	3	Retaining riparian buffer provides a carbon sink	3	35	4	Medium										
Vision 3: Resilient Infrastructure	V3.1 Replace undersized infrastructure	3	Significant flood risk reduction	9	3	Replacement can improve aquatic connectivity and ecosystem health	9	2	Contributes to community risk reduction	4	1	Indirect benefit, contributes to risk reduction	2	1	50 - 100 k for culvert replacements, 100 - 500 k for bridge replacements	1	2	For infrastructure replacements, assuming O&M already integrated into budget	2	3	Alignment with multiple funding programs. Aligned with existing capital planning/replacement and O&M	6	2	Routine work, in-water work may require additional regulatory approval	2	3	County in full control of action	3	1	Low/moderate GHG emissions	1	39	3	High										
	V3.2 Elevate roads along with crossing upgrades	1	Reduces flood risk for roads, but could increase upstream flood risk by forcing all the flow through culverts/bridges	3	0	No environmental benefits	0	2	Reduces flood damages to infrastructures but can increase flood levels upstream	4	3	Would reduce congestion during flood events, benefits for emergency response	6	1	Moderate capital cost	1	2	Non-capital cost similar to current conditions.	2	2	Alignment with multiple funding programs.	4	3	Routine work	3	3	County in full control of action	3	1	Low/moderate GHG emissions	1	27	5	Low										
	V3.3 Update the allowable stormwater discharge rate for new developments	1	Would contribute to reduced risk for new developments, but would not significantly impact risk on a watershed scale	3	2	Maintaining existing flow regime	6	1	Protects downstream landowners from increased flood risk	2	1	Reduced risk of property damage for downstream landowners	2	3	No capital cost	3	2	No increase in non-capital costs, minimal cost related to policy changes	2	3	Work to be completed internally	6	3	Minimal barriers to implementation	3	3	County in full control of action	3	2	No GHG emissions	2	32	4	Medium										
	V3.4 Incorporate flood construction level requirements in the LUB	3	Reduces flood risk for new developments	9	1	Reduces collateral pollution due to flooded buildings	3	3	Reduces flood damage and associated costs	6	3	Improves flood preparedness and reduces flood risk	6	3	No capital cost to update bylaws. Extra capital cost to raise structures above FCL. Variable cost based on lot elevation but still cheaper than flood damages	3	2	Low non-capital costs related to policy updates, education, and enforcement	2	3	Work to be completed internally	6	2	Low risk. Current bylaw already hold requirements regarding constructions in flood fringe.	2	2	County has full control of its bylaws, but some consultation might be required.	2	2	No GHG emissions	2	41	2	Very High										
	V3.5 Include climate change considerations in infrastructure and development standards/policy	3	Reduces flood risk.	9	1	Reduces collateral pollution due to flooded buildings	3	3	Reduces flood damage and associated costs	6	3	Improves flood preparedness and reduces flood risk	6	2	Slight increase in capital cost due to more stringent design criteria	2	2	Low non-capital costs related to policy updates, education, and enforcement	2	3	Work to be completed internally	6	3	Minimal risk with implementation	3	3	County owns the infrastructure	3	2	No GHG emissions	2	42	1	Very High										

Vision	Actions	Prioritization Criteria																										Action Prioritization																
		Contribution to flood/drought risk reduction				Environmental benefits				Economic benefits				Social benefits				Capital cost				Non-capital costs				Funding alignment & available resources				Ease of Implementation				Autonomy				Low-carbon resilience				Overall Priority Score	Priority ranking within vision	Overall Priority Level Based on Overall Priority Scores: Very Low: <25 Low: 25 - 29 Medium: 30-35 High: 36 - 40 Very High: >40
		Criteria Weight: 3		Score	Criteria Weight: 3		Score	Criteria Weight: 2		Score	Criteria Weight: 2		Score	Criteria Weight: 1		Score	Criteria Weight: 1		Score	Criteria Weight: 2		Score	Criteria Weight: 1		Score	Criteria Weight: 1		Score	Criteria Weight: 1		Score													
		Rationale	Weighted Score		Rationale	Weighted Score		Rationale	Weighted Score		Rationale	Weighted Score		Rationale	Weighted Score		Rationale	Weighted Score		Rationale	Weighted Score		Rationale	Weighted Score		Rationale	Weighted Score		Rationale	Weighted Score		Rationale	Weighted Score	Rationale	Weighted Score	Rationale	Weighted Score							
Vision 4: Proactive Management	V4.1 Implement a debris management program	2	Increase creek's conveyance capacity (assumed action taken throughout watershed)	6	1	Reduces collateral pollution due to flooded buildings. Depends on type, severity, and location of debris	3	2	Reduces flood damage and associated costs	4	3	Improves flood preparedness and reduces flood risk	6	3	No capital cost	3	1	Moderate annual cost, depends on extent of debris removal required	1	2	Work to be completed internally	4	3	Minimal risk with implementation, however landowner cooperation likely required for access	3	2	Land access would need to be granted	2	2	Minimal GHG emissions	2	34	2	Medium										
	V4.2 Expand asset management program	1	Well maintained/managed infrastructure less likely to fail in a flood event contributing to risk reduction	3	1	Prevention of flood/erosion risk associated with infrastructure failure	3	2	Regular maintenance can increase service life of infrastructure	4	2	Well maintained infrastructure will continue to provide required level of service to residents	4	3	Although asset management program may lead to capital spending, this is not directly associated with asset management program	3	2	Moderate increase in non-capital costs to expand and continue asset management program. Costs will likely be higher in the short term while program is developed, and less over time as program becomes operational	2	2	Possible funding alignment, assuming expansion of existing asset management program using internal resources	4	3	Minimal risk with implementation, expansion of existing program	3	3	County is in full control of action	3	2	Minimal GHG emissions	2	31	3	Medium										
	V4.3 Proactive creek inspections and monitoring	1	Improved flood preparedness contributes to reduced risk consequence	3	1	Prevention of flood/erosion risk associated with infrastructure failure	3	1	Improve emergency preparedness can reduce flood costs/damage	2	2	Improves flood preparedness	4	3	No capital cost	3	2	Low increase in non-capital cost	2	2	Work to be completed internally	4	3	Minimal risk with implementation, however landowner cooperation likely required for access	3	2	Land access would need to be granted	2	2	Minimal GHG emissions	2	28	4	Low										
	V4.4 Landowner education and partnership for private property clean up	2	Increase creek's conveyance capacity (assumed landowner participation across watershed which would contribute to overall risk reduction)	6	1	Reduces collateral pollution due to flooded buildings.	3	2	Reduces flood damage and associated costs	4	3	Improves flood preparedness and reduces flood risk	6	3	No capital cost	3	2	Minimal non-capital costs related to support and education for landowners	2	3	Internal costs	6	2	Minimal risk with implementation, however success will depend on landowner buy-in and participation	2	1	Fully dependent on stakeholder collaboration	1	2	Minimal GHG emissions	2	35	1	Medium										
Vision 5: Emergency Preparedness	V5.1 Develop flood response plan and training	2	Improve flood preparedness and response helps to reduce risk consequence	6	0	No environmental benefits	0	2	Improve flood response and reduces damages	4	2	Reduced risk and improved overall flood response, contributes to improved public safety	4	3	No capital cost	3	2	Low increase in non-capital cost (less than \$50k)	2	2	Potential funding, internal resources	4	3	Minimal risk with implementation	3	1	High level of partnership required for a coordinated response	1	2	No GHG emissions	2	29	3	Low										
	V5.2 Develop flood forecast, monitoring, and warning system	2	Improve flood preparedness and response helps to reduce risk consequence	6	0	No environmental benefits	0	2	Improve flood response and reduces damages	4	2	Reduced risk and improved overall flood response, contributes to improved public safety	4	2	Less than \$75k for an hydrometric station	2	2	Low increase in non-capital cost (less than \$50k)	2	2	Potential funding, internal resources	4	3	Minimal risk with implementation	3	2	Land access might be required for hydrometric station installation.	2	2	Minimal GHG emissions	2	29	3	Low										
	V5.3 Develop a drought mitigation plan	2	Improve drought preparedness helps to reduce risk consequence	6	1	Drought preparedness likely to incorporate improved water retention	3	2	Helps to reduce financial impacts of drought	4	2	Improves drought preparedness	4	3	No capital cost	3	2	Low non-capital costs	2	2	May be eligible for funding to support plan development, some internal County resources could also support	4	3	Minimal barriers to implementation	3	3	County is in full control of action	3	2	No GHG emissions	2	34	2	Medium										
	V5.4 Increase public understanding of flood prevention and drought mitigation, property protection and emergency response	2	Increases preparedness and reduced risk consequence as residents will have been engaged in development of risk/response plans	6	0	No environmental benefits	0	2	Residents understanding and preparing for flood/drought can help to reduce damages	4	3	Increase in residents' understanding of risks and increases buy in for mitigation measures to reduce risk to public safety and property damage	6	3	No capital cost	3	2	Low non-capital costs	2	3	Anticipated to be covered within existing County resources	6	3	Minimal barriers to implementation	3	2	County can initiate action, however, participation of citizens is required	2	2	Minimal GHG emissions	2	34	2	Medium										
	V5.5 Incentivize property level flood protection	3	Decreased property flood risk	9	2	Reduces collateral pollution due to flooded buildings	6	3	Reduces flood damage and associated costs	6	3	Improves public safety	6	2	Low capital cost to County to provide incentive. Moderate capital cost to landowners.	2	2	Low non-capital costs	2	1	Possible funding through partnership applications	2	2	Minimal risk with implementation, however success will depend on landowner buy-in and participation	2	1	County can implement incentive program, however action implementation is dependent on property owners	1	2	Minimal GHG emissions	2	38	1	High										
	V5.6 Investigate availability of flood insurance for landowners	0	No direct impact on risk reduction	0	0	No environmental benefits	0	2	Sharing of flood damage cost between policy owners. Reduce risk to property value.	4	1	Localized benefits for homeowners with insurance. Increased awareness of insurance availability and options.	2	3	No capital cost.	3	2	Minimal cost to county to provide information to landowners. Possibility of increased insurance premiums for land owners.	2	0	No funding available.	0	1	Insurance availability uncertain.	1	1	County can provide support and information, but action is dependent on property owners	1	2	No GHG emissions	2	15	4	Very Low										
Vision 6: Educated, engaged, and empowered public	V6.1 Implement public outreach programs	0	No direct impact on risk reduction	0	1	Increased environmental awareness	3	1	Increased risk awareness contributes to support for mitigation to reduce damages	2	3	Strengthen community connections, foster support for resilience initiatives	6	3	No capital costs associated with action	3	2	Low non-capital costs, cost would be incurred over time	2	3	Funding programs available (community conservation action program), also in alignment with internal operating budget	6	3	Minimal barriers to implementation	3	2	County in full control of action, although there may be additional benefits to partnership	2	2	Minimal GHG emissions	2	29	3	Low										
	V6.2 Implement pilot programs to showcase nature-based solutions	1	Localized flood reduction via pilot	3	2	Localized environmental benefit	6	1	Localized property risk reduction or community damages	2	2	Localized benefit, depends on communication of project	4	3	Majority of pilot projects will be less than \$10k	3	2	Low non-capital costs, cost would be incurred over time	2	3	Funding programs available (EcoAction, NatureSmart, Watershed Stewardship Grant)	6	2	Perceived risk from up and downstream landowners. Assumption: need one pilot landowner to agree	2	2	Likely need at least one landowner for access	2	2	Minimal/no GHG emissions in most cases, some could be GHG sinks	2	32	1	Medium										
	V6.3 Implement citizen science initiatives	0	No direct impact on risk reduction	0	1	Increased environmental awareness and availability of data to monitor/improve environmental outcomes	3	1	Indirect economic benefit as County will know more about private and public lands	2	3	Strengthen community connections, foster support for resilience initiatives, build science and data capacity	6	3	No capital costs associated with action	3	2	Low non-capital costs, cost would be incurred over time	2	3	Funding programs available (community conservation action program), also in alignment with internal operating budget	6	3	Minimal barriers to implementation	3	2	Success depends on engagement of citizens	2	2	Minimal/no GHG emissions	2	29	3	Low										
	V6.4 Indigenous relations	0	No direct impact on risk reduction	0	1	Increased environmental awareness and understanding of different perspectives for environmental management	3	2	Improved relations fosters improved future decisions/collaboration around creek management and consultation	4	3	Both County and Indigenous communities stand to benefit from improved relations. Opportunity to align with implementation of Vision 1.	6	3	No capital costs associated with action	3	2	Low non-capital costs	2	3	Improves access to additional grants and programs	6	2	Low risk, largely perceived. County is already active in ongoing Indigenous Relations programs	2	2	County can initiate actions, but collaboration/involvement from Indigenous communities is required for success	2	2	Minimal GHG emissions	2	30	2	Medium										



PROJECT RECOGNITION

C



2022
SHOWCASE
- AWARDS -

AWARD OF
EXCELLENCE
-
ENVIRONMENTAL



ASTOTIN CREEK RESILIENCY STUDY

AWARD OF EXCELLENCE
Environmental

FIRM: WSP

CLIENT/OWNER: STRATHCONA COUNTY

LOCATION: STRATHCONA COUNTY, ALBERTA

SUB CONSULTANTS: UNIVERSITY OF ALBERTA,
INNOTECH

Multiple severe floods in Astotin Creek over the past decade triggered the need for an interdisciplinary study to develop a Watershed Resiliency Action Plan. WSP's study balanced environment, engagement, and engineering to create a healthy watershed. The analysis incorporated vegetation, soils, wildlife, fish and aquatic habitat, surface and groundwater studies, climate analysis, innovative eDNA and modeling techniques plus extensive public engagement. This robust assessment will lead to a holistic resiliency action plan with a focus on nature-based solutions. The goal is a community supported plan which enables both residents and Mother Nature to thrive. Study partners: University of Alberta and InnoTech

JUDGES' COMMENTS

The Astotin watershed study creates practical tangible recommendations for managing the watershed, that were founded on community support and feedback.

Figure C-1: Astotin Creek Award Announcement (Consulting Engineers of Alberta, Alberta Innovators Magazine, Spring 2022 issue, page 48)